


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 36 Twp. 22 Rge. 13 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines NE NE SW
Lease Owner McAdams Pipe & Supply Co.
Lease Name Long #1 Well No. _____
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9-11-58 19____
Plugging completed 9-19-58 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3813' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	256'	none
				5-1/2"	3812'	2862'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 3813' and found it open.
Filled w/sand to 3800' and dumped 5 sacks of cement. Pulled 49 jts of 5 1/2" casing and pumped in 10 sacks of gel mud. Pulled rest of casing, cleared hole and bailed fluid, to 240', set a 10' rock bridge and dumped 20 sacks of cement. Mudded the hole to 35', set a 10' rock bridge and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECEIVED
STATE CORPORATION COMMISSION
SEP 25 1958

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
I, Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of September, 19 58

9-27-58

T. Thomas V. Duggins
Notary Public.

My commission expires _____

PLUGGING
FILE SEC 36 T 22 R 13w
BOOK PAGE 128 LINE 40


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

ARNOLD KIMMIS, WILD CAT URANIUM &
Company- WORLD URANIUM
Farm- Long No. 1

SEC. 36 T. 22 R. 13W
NE NE SW

Total Depth. 3813
Comm. 4-7-55 Comp. 4-16-55
Shot or Treated.
Contractor, Shawver-Armour, Inc.
Issued. 7-16-55

County Stafford
KANSAS



Elevation. 1880 DF

Production. 237 BOPD

CASING:
8 5/8 256' w/ 265 sx cmt.
5 1/2 3812' w/ 125 sx cmt.

Figures indicate Bottom of Formations

sand & clay	185
clay & shale	256
red bed, shale & shells	1175
shale	1880
lime	2235
shale & lime	2570
shale	2860
shale & lime	3415
lime	3515
lime & shale	3584
lime	3610
lime & shale	3793
sand & lime	3813
Total Depth	

TOPS:	
Heebner	3236
Brown lime	3272
Lansing	3388
Viola	3667
Simpson	3740
Arbuckle	3801

RECEIVED
STATE CORPORATION COMMISSION

SEP 11 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 36 T. 22 R. 13W
BOOK PAGE 128 LINE 40