

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Stafford County. Sec. 31 Twp. 22 Rge. 14 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SE SE
Lease Owner Petroleum, Inc.
Lease Name McMillan 'A' Well No. 1
Office Address 305 East Third, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 29, 19 53
Application for plugging filed September 29, 19 53
Application for plugging approved September 29, 19 53
Plugging commenced September 29, 19 53
Plugging completed September 29, 19 53
Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M.A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4,104 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	200'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 200' and set wooden plug

at 200'. Placed 1/4 sack hulls on top

of plug at 200'. Cemented and displaced

20 sacks cement through drill pipe, no

fluid above plug, onto plug and hulls at

200'. Mudded up to 40' and set second

wooden plug at 40'. Filled hole to bottom

of well cellar with 10 sacks cement.

10-6-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company

Address R.R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

W.W. Fisher (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)


305 East Third, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of October, 19 53

My commission expires October 13, 1954

Notary Public.

24-7368-5 3-53-20M



DRILLER'S LOG McMILLAN 'A' #1

Petroleum, Inc., Operator

Section 31, Twp. 22S, Rge. 11W

Garvey Drilling Company, Contractor

Location: SW SE SE

Drilling Commenced: September 18, 1953

County: Stafford County, Kansas

Drilling Completed: September 29, 1953

Production: D & A

Casing Record: 8 5/8" @ 200' w/200 sax

R.T.D.: 4104'

Figures below indicate bottom of formation:

90	Surface & Sand
135	Coarse Sand & Shale
265	Shale & Shells
830	Red Bed & Sand Streaks
893	Red Bed
925	Anhydrite
1815	Shale & Shells
3539	Lime & Shale
3880	Lime
3934	Chert
3940	Shale
3978	Shale
4051	Shale & Lime
4054	Shale
4104	Lime
4104	R.T.D.

Tops:

Heebner:	3417(-1447)
Toronto:	3439(-1469)
Douglas:	3455(-1485)
Brown Lime:	3549(-1579)
Lansing:	3560(-1590)
Conglomerate:	3878(-1908)
Viola:	3886(-1916)
Simpson:	3934(-1964)
Arbuckle:	4054(-2084)

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By W. W. Fink

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 5th day of October, 1953.

Charles E. Freeman
 Notary Public

My commission expires: October 13, 1954

