

15.083.10210.00.00

Form CP-3
Rev. 6-26-62

JP
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Misco Leasing, Inc.

Complete Address: 101 Misco Bldg., Wichita, Kansas

Lease Name Weiland "A" Well No. 2

Location C NE SW Sec. 16 Twp. 21 Rge. 22 (~~E~~) (W)

County Hodgeman Total Depth 4450'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Comstock Pipe Pulling Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 11:00AM Day 22 Month 2 Year 1968

The Above well was plugged as follows:

8 5/8" to 273' circulated w/cement. 4 1/2" to 4441' cemented.

Top perforations 4284' Bottom plugged w/ sand to 700'

Plug & 50 sacks cement 688' to 500' Mud 500' to 350'

100 sacks cement 350' to 0' Haliburton Pump Truck.

Had hole in 4 1/2" casing at 700', Casing filled w/ sand to this point.

Pulled 688' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edward J. Eves*
Well Plugging Supervisor

DATE 2/26/68
INV. NO. 9325-W