

15.083.20163.00.00

Form CP-3
Rev. 6-4-68

KANSAS

70
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum Inc.

Complete Address 300 W. Douglas, Wichita, Kansas

Lease Name Bamberger "C" Well No. 1

Location C SE NE Sec. 26 Twp. 21 Rge. 23 (E) (W)

County Hodgeman Total Depth 4595'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Garvey Drilling Co.

Address Rt. 2, Great Bend, Kansas License No.

Operation Completed: Hour 5:00PM Day 21 Month 6 Year 1971

The above well was plugged as follows:

8 5/8" to 350' circulated w/ cement. Mud 4595' to 800'

Spotted 80 sacks cement 800' to 500' Mud 500' to 350'

Spotted 30 sacks cement 350' to 250' Mud 250' to 45'

Plug. Halls & 15 sacks cement 45' to 0'. Globe Cementing Pump Truck

I hereby certify that the above well was plugged as herein stated.

Signed: *Edward J. Lee*
Well Plugging Supervisor

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1971
CONSERVATION DIVISION
Wichita, Kansas
INVOICED
DATE 6/30/71
INV. NO. 3919-W