

15.083.00275.00.00

Form CP-3  
Rev. 6-26-62

SP

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 17 1964

CONSERVATION DIVISION  
Wichita, Kansas

8-17-1964

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name Adams "F" Well No. #.1

Location C NW SE Sec. 20 Twp. 21 Rge. 24 (E) (W) W

County Hodgeman Total Depth 4540

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A      X     

Other well as hereafter indicated:     

Plugging Contractor: Comstock Pipe Pulling Inc.

Address: Stafford, Kansas License No.     

Operation Completed: Hour 2:00PM Day 13th Month August Year 1964

The Above well was plugged as follows:

442' of 8 5/8" surface pipe, cement circulated. 4437' of 5 1/2" long string,  
cemented. Plug back to 4315'. Top perforation 4223'. Bottom of the hole  
was cemented with 20 sacks.

At 700', 15 sacks of Gel-Mud and 25 sacks of cement was pumped into 5 1/2"  
casing, through a swage. Pipe was pulled up to 400', and 25 sacks of  
cement was pumped, through 5 1/2" swage. Fluid was bailed down to 45', and  
a bridge plug was set on fluid, and cemented with 15 sacks to the base

of the cellar. 2603' of 5 1/2" long string was recovered from the hole. This  
cementing was done by Globe Cementing Company.

Hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Achie Elving  
Well Plugging Supervisor

DATE 8-18-64  
INV. NO. 9652-W