

4-060815

15-009-15060-00-01

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- -11-05-53

1-3
VCC
NCC
SW SW ^{NE} /4 SEC. 29, 16 S, 11 W
3302970 feet from S section line
49502310 feet from E section line

Operator license# 4252

Lease: Seyfert "A" Well # 11

Operator: Kahan & Associates, Inc.

County: Barton

Address: P.O. Box 700780
Tulsa, OK 74170

Well total depth 3311 107.61 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 350 feet

Aband. oil well X, Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Mike's Testing and Salvage, Inc. License# 31529

Address: P.O. Box 209 - Chase, Kansas 67524

Company to plug at: Hour: 9:00 A.M. Day: 3 Month: January Year: 1996

Plugging proposal received from: Mike Kelso

Company: Mike's Testing and Salvage, Inc. Phone: 316-938-2943

Were: Order 250 sxs 60/40 posmix - 10% gel and hulls.
Plug while pulling casing.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 1:15 P.M., Day: 3, Month: January, Year: 1996

Actual plugging report: 8 5/8" to 350' with 240 sxs. 5 1/2" to 3308' with 250 sxs. Perfs from 2800' - 3311'. Sanded to 2750' and spotted 5 sxs cement with dump bailer. Shot casing at 2000' - 1600' - 1200' - 800' with no recovery. Shots solid indicating cement squeeze possible. Mixed and pumped 70 sxs cement with 300# hulls and displaced to 700'. Shot casing at 600' and 429' with 429' loose. Mixed and pumped 40 sxs cement with 100# hulls. Pulled casing to 250' and circulated cement with 40 sxs cement with 100# hulls. Pulled casing and topped with 40 sxs cement.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD _____ Any plug: YES X NO _____
Bottom plug(in place): YES X, CALC _____, NO _____ Dakota plug: YES X REC'D NO _____
Plugged through TUBING _____, CASING X. Elevation: 1888

I did[] / did not[X] observe the plugging.

INVOICED

DATE JAN 23 1996

WOL NO. 44687

RECEIVED
STATE CORPORATION COMMISSION
JAN 23 1996
(agent)
Form CP-2/3
WICHITA, KANSAS