

1 050879

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-145-21,117-0000

S/2 SE SW, SEC. 10, T 22 S, R 15 W/E

990 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6139

Lease Name Compton "A" Well # 1

Operator: Jay C. Boyer

County Pawnee 130.26

Name & Address P.O. Box 511

Well Total Depth 4008 feet

Hays, KS 67601

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 645

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 2 Month: 2 Year: 19 87

Plugging proposal received from Mark McCabe

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 3824' PBTD 3781' Perfs at 3658-63' Elevation 1988' GL

1st plug pump 1 sx hulls and 20 sx cement to 3600',

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 125 sx cement.

Plugging Proposal Received by Richard Lacey and Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 2 Month: 2 Year: 1987

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement to 3600',

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 4 1987

Maximum pressure 800 psi and shut in 200 psi.

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Recovered 2225' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If desired, check box) observe this plugging.

DATE 2-4-87

Signed Richard W. Lacey  
(TECHNICIAN)

INV. NO. 16074