

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-145 - 21,097-0000  
SE 1/4, Sec. 24, T 22 S, R 16 W/X  
990 feet from N/~~X~~ section line SE 1/4  
330 feet from ~~N~~/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5273

Lease Name Crawford Well # 1

Operator: Kiowa Exploration Co.  
Name & 420 Heritage Park Place  
Address 110 S. Main  
Wichita, KS 67202

County Pawnee  
Well Total Depth 4040 feet 131.30  
Conductor Pipe: Size        feet  
Surface Casing: Size 8 5/8 feet 628

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D&A X

Other well as hereinafter indicated       

Plugging Contractor J.W. Drilling Co. License Number 5137

Address 200 E. First, # 500, Wichita, KS 67202

Company to plug at: Hour: 7:00 am Day: 21 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Bill Roach

(company name) J.W. Drilling (phone) 316-263-5705

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 4000' with 50 sx cement

2nd plug at 960' with 50 sx cement

solid bridge

3rd plug - hulls - plug at 40' -- cement to surface with 10 sx cement

5 plug - to circulate rathole with 15 sx cement. Plug water well with

5 sx cement.

Signed Paul A. Luthin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All        Part        None X

Operations Completed: Hour: 12:30 pm Day: 21 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 4000' with 50 sx cement, 2nd plug at 960' with

50 sx cement, 3rd plug - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement. circulate rathole with 15 sx cement. Plug water well with

5 sx cement.

Remarks: Use 60/40 Pozmix, 2% gel, by Sun Cementing

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

Signed Paul A. Luthin  
(TECHNICIAN)

INVOICED

RECEIVED  
STATE CORPORATION COMMISSION

DATE 2-1-84

JAN 26 1984

INV. NO. 9307 W

1-26-84

CONSERVATION DIVISION  
Wichita, Kansas