

3-10-88

1 051017

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,502-0000

SE NE NW, SEC. 32, T 22 S, R 13 W&E

4290 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6484

Lease Name Hahn Well # 1

Operator: Thornton E. Anderson

County Stafford 125.94

Name & Address 212 North Market, Suite 508

Well Total Depth 3875 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 284

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Western Kansas Drilling License Number 4083

Address Box 126, Hays, KS 67601

Company to plug at: Hour: 6 a.m. Day: 10 Month: 3 Year: 1988

Plugging proposal received from Frank Tagett

(company name) Western Kansas Drilling (phone) 913-628-2296

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 788-811'

1st plug at 810' with 50 sx cement, 2nd plug at 310' with 40 sx cement,

3rd plug at 40' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

_____ Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8 a.m. Day: 10 Month: 3 Year: 1988

ACTUAL PLUGGING REPORT 1st plug at 810' with 50 sx cement,

2nd plug at 310' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
3-14-88
MAR 14 1988

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

If (plug / did not) observe this plugging.

Signed Richard M. Lacey
(TECHNICIAN)

INVOICED
DATE 3-16-88
INV. NO. 20107
3-10

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. March 3, 1988
month day year

API Number 15-185-22,502-0000

OPERATOR: License # 6484
Name Thornton E. Anderson
Address 212 N. Market, Suite 508
City/State/Zip Wichita, KS 67202
Contact Person William L. Anderson
Phone 316/265-7929

SE NE NW Sec. 32 Twp. 22 S, Rg. 13 East
4290 West
2970 Ft. from South Line of Section
Ft. from East Line of Section

CONTRACTOR: License # 4083
Name Western Kansas Drilling
City/State Hays, KS 67601

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 330 feet
County Stafford
Lease Name Hahn Well # 1
Ground surface elevation 1909 feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Depth to bottom of fresh water 230
Depth to bottom of usable water 230
Surface pipe by Alternate: 1 2
Surface pipe planned to be set 250
Conductor pipe required N/A
Projected Total Depth 3850 feet
Formation Arbuckle

Well Drilled For: Well Class: Type Equipment:
 Oil Storage Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 2/26/88 Signature of Operator or Agent William L. Anderson Operations Manager

For KCC Use:
Conductor Pipe Required 250 feet; Minimum Surface Pipe Required 250 feet per Alt.
This Authorization Expires 3-29-88 Approved By RCH 2-29-88

EFFECTIVE DATE: 3-5-88
Set 8 5/8 at 284 on 3-4-88

SE NE NW Sec. 32 Twp. 22 S, Rg. 13 East
West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep... Anhydrite 25 SX feet of... cement
2nd plug @ ft. deep... 250 40 SX feet of... cement
3rd plug @ ft. deep... 40 10 SX feet of... cement
4th plug @ ft. deep or formation with feet of.....
5th plug @ ft. deep or formation with feet of.....

(2) Rathole to surface minus 5 feet (b) Mousehole to surface minus 5 feet

PUSHER Franck Taggart
TD 3825 FORMATION Viola
SURFACE PIPE 8 5/8 @ 284
ANHYDRITE 288-811 ELEVATION
STARTING TIME & DATE 1:00a 3-10-88
COMPLETION TIME & DATE 8:00a 3-10-88
1st PLUG @ 50 FT. WI 50 SX
2nd PLUG @ 810 FT. WI 50 SX
3rd PLUG @ 310 FT. WI 40 SX
4th PLUG @ 40 FT. WI 10 SX
RAT HOLE CIRCULATED WI 15 SX
MOUSE HOLE CIRCULATED WI 10 SX
WATER WELL PLUGGED WI
CEMENT COMPANY Allied
TECHNICIAN R. L.
60/40 poz 6 page 1

RECEIVED
STATE CORPORATION COMMISSION
MAR 14 1988
CONSERVATION DIVISION
Wichita, Kansas