

To: 1 070607
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-/
API NUMBER 15- 185-22,553-0000
SW SE SW, SEC, 24, T 22 S, R 13 W ~~XX~~

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422
Operator: Abercrombie Drilling, Inc.
Name & Address 801 Union Center
Wichita, KS 67202

330 feet from S section line
3630 feet from E section line
Lease Name State Well # 1
County Stafford 123.18
Well Total Depth 3790 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 321

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling Inc. License Number 5422
Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 3:30 a.m. Day: 1 Month: 11 Year: 19 88

Plugging proposal received from Harvey Moore
(company name) Abercrombie Drilling Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1880'
Anhydrite 727-747'

- 1st plug at 745' with 50 sx cement,
- 2nd plug at 340' with 40 sx cement,
- 3rd plug at 40' with 10 sx cement,
- 4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 a.m. Day: 1 Month: 11 Year: 19 88

- ACTUAL PLUGGING REPORT 1st plug at 745' with 50 sx cement,
- 2nd plug at 340' with 40 sx cement,
- 3rd plug at 40' with 10 sx cement,
- 4th plug to circulate rathole with 15 sx cement,
- Water well plugged with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1988

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 11-21-88
INV. NO. 23032
11-1

Signed Dan Goodrow
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date..... 10 24 88
month day year

API Number 15-185-22,553-0000

OPERATOR: License # 5422
Name Abercrombie Drilling, Inc.
Address 801 Union Center
City/State/Zip Wichita, KS 67202
Contact Person Jack L. Partridge
Phone (316) 262-1841

SW SE SW Sec. 24 Twp. 22 S, Rg. 13 East
330 West
3630 Ft. from South Line of Section
Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet
County Stafford

Lease Name State Well # 1
Ground surface elevation feet MSL

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

Depth to bottom of fresh water 140'
Depth to bottom of usable water 250' 280'

Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 300'

Conductor pipe required
Projected Total Depth 3775' feet

Formation Arbuckle

CONTRACTOR: License # 5422
Name Abercrombie Drilling, Inc.
City/State Wichita, KS

Well Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
Gas Inj X Pool Ext. Air Rotary
OWWO Expl Wildcat Cable

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 10-21-88 Signature of Operator or Agent Title Vice President

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 300 feet per Alt. 1 X
This Authorization Expires 1-21-89 Approved By 10-21-88

EFFECTIVE DATE: 10-26-88

SW SE SW Sec. 24 Twp. 22 S, Rg. 13 East
X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep. Base Anhydrite or formation with 30 SX feet of 60/40 pos., 6% gel., 3% cc.
2nd plug @ ft. deep. Mid Anhydrite or formation with 35 SX feet of 60/40 pos., 6% gel., 3% cc.
3rd plug @ ft. deep. Base Dakota or formation with 100 SX feet of 60/40 pos., 6% gel., 3% cc.
4th plug @ ft. deep. 350' or formation with 50 SX feet of 60/40 pos., 6% gel., 3% cc.
5th plug @ ft. deep. 40' or formation with 10 SX feet of 60/40 pos., 6% gel., 3% cc.

(2) Rathole to surface minus 5 feet 10-15 with 60/40 pos, 6% gel (b) Mouschhole to surface minus 5 feet

PUSHER Harvey Moore
TD 3190 FORMATION 206
SURFACE PIPE 8 5/8" @ 321'
ANHYDRITE 727' ELEVATION 1800'
STARTING TIME & DATE 3:30 AM 11-1-88
COMPLETION TIME & DATE 5:30 AM
1st PLUG @ 745 FT. W/ 50 SX
2nd PLUG @ 340 FT. W/ 40 SX
3rd PLUG @ 40 FT. W/ 10 SX
4th PLUG @ FT. W/ SX
60/40 6% gel
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ 10 SX
CEMENT COMPANY Allied
TECHNICIAN

If more 50' in Arb.
RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1988
OBSERVATION DIVISION
Wichita, Kansas