

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22576-00-00
Spot: SWSSEW Sec/Twnshp/Rge: 4-22S-11W
330 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: FAIR B Well Number: 5
County: STAFFORD Total Vertical Depth: 3600 feet

Operator License No.: 3842 Production Casing Size: 5.5 feet: 3573 WITH 150 SX CMT
Op Name: LARSON ENGINEERING INC DBA LARS Surface Casing Size: 8.625 feet: 304 WITH 225 SX CMT
Address: 562 WEST HIGHWAY 4
OLMITZ, KS 67564

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/12/2003 9:45 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: VERNON PFLUGHOEFT Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: SAND TO 3290' WITH 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/12/2003 11:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:


PBTD 3522'. PERFS AT 3442-43, 3434-40, 3342-46'. SAND BACK TO 3230' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. (300# HULLS MIXED IN WITH GEL & CMT). 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20' SX CMT.

RECEIVED
AUG 22 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2600' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)
INVOICED

DATE 9-2-03
INV. NO. 2004060453

Form CV-275