

To: 1 121102
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

15-185-30203-6000
API NUMBER 15- Drilled 1965
SE SW SW, SEC. 4, T 22 S, R 11 W/EX
330 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3842
Operator: Larson Operating Company
Name & Address: 562 W. Highway 4
Olmitz, KS 67564-8561

Lease Name Fair B Well # 4
County Stafford 114.56
Well Total Depth 3525 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 292

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Larson Operating Company License Number 3842

Address 562 W. Highway 4, Olmitz, KS 67564-8561

Company to plug at: Hour: 1 p.m. Day: 22 Month: 1 Year: 1996

Plugging proposal received from Tom Larson

(company name) Larson Operating Co. (phone) 316-653-7368

were: 5 1/2" at 3515' w/140 sx cement. Perfs at 3188-3448' (11 sets)

1st plug set CIBP at 3100' and dump 4 sx cement on top with bailer,

2nd plug perforate 5 1/2" casing at 485' and circulate cement with 150 sx.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3 p.m. Day: 22 Month: 1 Year: 1996

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3100' and dumped 4 sx cement on top with bailer,

2nd plug perforated 5 1/2" casing at 485' and circulated with 150 sx cement.

RECEIVED
KANSAS CORP COM 1
1996 JAN 26 P 12:18

1-26-96

Remarks: Used common cement by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Duane Rankin
(TECHNICIAN)

DATE 1-30-96

INV. NO. 44254

1-22