

1 120262

6-7 15-185-10840-0002

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-24,579

SE SE SW, SEC. 4, T 22 S, R 11 W/E

330 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3613

Lease Name Fair "B" Well # 2

Operator: Quinoco Petroleum, Inc.

County Stafford 124.83

Name & Address P.O. Box 378111

Well Total Depth 3841 feet

Denver, CO 80237

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 182

Abandoned Oil Well _____ Gas Well _____ Input Well x SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Quinoco Petroleum, Inc. License Number 3613

Address P.O. Box 378111, Denver, CO 80237

Company to plug at: Hour: 12:30 p.m. Day: 7 Month: 6 Year: 19 89

Plugging proposal received from George Hutton

(company name) Quinoco Petroleum, Inc. (phone) 316-792-2756

were: 5 1/2" at 3696' Perfs at 3197-3841' (5 sets) below 3200' during work over. Drilled out of 5 1/2" casing in perforations

1st plug sand back to 3640' and run tubing to 3640',

2nd plug pump 30 sx gel and 60 sx cement,

3rd plug pull tubing to 500' and spot 56 sx cement to 0'.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 7 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3067' and ran 2 3/8" tubing to 3041',

2nd plug pumped 60 sx cement, laid down 25 joints of 2 3/8" tubing, 6-13-89

3rd plug pumped 20 sx gel, laid down 54 joints of 2 3/8" tubing, RECEIVED

4th plug circulated cement to top of 5 1/2" with 50 sx cement, STATE CORPORATION COMMISSION

5th plug laid down all 2 3/8" tubing and filled 5 1/2" casing with 10 sx cement. JUN 13 1989

Remarks: Used 60/40 Pozmix 8% gel by HOWCO. No casing recovery. CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 6-14-89

Signed Duane Rankin (TECHNICIAN)

INV. NO. 25065