

1 050945

10-21-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200' COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,469-0000
SE NE NW, SEC. 3, T 22 S, R 11 W/K
4280 feet from S section line
3280 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9121

Lease Name Eriksen Well # 1

Operator: Kiwanda Energy, Inc.

County Stafford 114.37

Name & Address P.O. Box 1320

Well Total Depth 3519 feet

Wichita, KS 67201

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor H-30 Drilling License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 3 a.m. Day: 21 Month: 10 Year: 19 87

Plugging proposal received from Rick Davis

(company name) H-30 Drilling (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1804' GL
Anhydrite 460-81'

1st plug at 720' with 40 sx cement,

2nd plug at 330' with 50 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 a.m. Day: 21 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 720' with 40 sx cement,

2nd plug at 330' with 50 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 22 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

INVOICED

do not observe this plugging.

DATE 10-28-87

Signed Richard W. Lucy
(TECHNICIAN)

INV. NO. 18688

10-21

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... 10/9/87 month day year

API Number 15-185-22,469-0000

OPERATOR: License # 9121 Name: Kiwanda Energy, Inc. Address: P.O. Box 1320 City/State/Zip: Wichita Kansas 67201 Contact Person: C. Kirk Fraser Phone: (316) 267-2697

APP/SE NE NW Sec. 3 Twp. 22 S, Rg. 11 East West 4280 3280 Ft. from South Line of Section Ft. from East Line of Section

CONTRACTOR: License # 5107 Name: H-30 City/State: Wichita Kansas

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 1000 feet County: Stafford

Well Drilled For: Well Class: Type Equipment: X Oil Storage Infield X Mud Rotary Gas Inj X Pool Ext Air Rotary OWWO Expl Wildcat Cable

Lease Name: ERIKSEN Well # 1 Ground surface elevation: NA feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Depth to bottom of fresh water: 100 Depth to bottom of usable water: 175 Surface pipe by Alternate: 1 X 2 Surface pipe planned to be set: 250 Conductor pipe required Projected Total Depth: 3500 feet Formation: Arbuckle

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date: 10/7/87 Signature of Operator or Agent: C. Kirk Fraser (M.V.) Title: President

For KCC Use: Conductor Pipe Required: 250 feet; Minimum Surface Pipe Required: 250 feet per Alt. 1 X This Authorization Expires: 4-7-88 Effective: 10-12-87 Approved By: Rich Davis 10-7-87

Rich Davis Move in 10-16-87 set 250 ft of 8 5/8" WW

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep... 750 or formation with... 75 60/40 poz. 2nd plug @ ft. deep... 300 or formation with... 25 60/40 poz. 3rd plug @ ft. deep... 40 or formation with... 10 w/bridge 60/40 poz. 4th plug @ ft. deep... 27 or formation with... feet of... 5th plug @ ft. deep... 21 or formation with... feet of... (2) Rathole to surface minus 5 feet (b) Mousehole to surface minus 5 feet

PUSHER Rich Davis TD 3519 FORMATION Arbuckle SURFACE PIPE 8 5/8 @ 302 ANHYDRITE 460 ELEVATION 180468 STARTING TIME & DATE 3:00 on 10-21-87 COMPLETION TIME & DATE 4:30 on 10-21-87 1st PLUG @ 720 FT. W/ 40 SX 2nd PLUG @ 330 FT. W/ 50 SX 3rd PLUG @ 40 - 0FT. W/ 10 SX 4th PLUG @ FT. W/ SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ gave to Federal Range CEMENT COMPANY B. J. Latham TECHNICIAN Paul Luthi 60/40 w/ 6% gel

STATE COMMISSION

OCT 22 1987

CONSERVATION DIVISION Wichita Kansas