

To: 1 121101
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION App. 1-22
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-185-20,874-0002
SE NW NW, SEC. 3, T 22 S, R 11 W/XX
4125 feet from S section line
4240 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3842
Operator: Larson Operating Company
Name:
Address 562 W. Highway 4
Olmitz, KS 67564-8561

Lease Name Eriksen Well # 1-3
County Stafford 112.45
Well Total Depth 3460 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 469

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Larson Operating Company¹ License Number 3842

Address 562 W. Highway 4, Olmitz, KS 67564-8561

Company to plug at: Hour: 10 a.m. Day: 22 Month: 1 Year: 1996

Plugging proposal received from Tom Larson

(company name) Larson Operating Company (phone) 316-653-7368

was: 4 1/2" at 3459' w/150 sx cement, PBSD 3316', Perfs at 3250-56, 3350-56, CIBP @ 3390, 3410-16, CIBP @ 3439', Open hole 3459-60'

1st plug set CIBP at 3200' and dump 4 sx cement on top. Fill 4 1/2" casing with mud and perforate 4 1/2" casing at 517', 2nd plug circulate cement to bottom of cellar with 180 sx.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 22 Month: 1 Year: 1996

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3200' and dumped 4 sx cement on top with bailer, Filled 4 1/2" casing with mud and perforated 4 1/2" casing at 517'.

2nd plug circulated cement to bottom of cellar with 180 sx cement.

RECEIVED
KANSAS CORP COMMISSION
1996 JAN 26 P 12:18

1-26-96

Remarks: Used common cement by Allied. No casing recovery.
(if additional description is necessary, use BACK of this form.)

I (the undersigned) observe this plugging.

DATE 1-30-96

INV. NO. 44755

Signed Duane Rankin (TECHNICIAN)

1-22