

3 022363

15-207.19141-000

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER _____
SW,NW,NW 1/4 Sec/Twp/Rge S.28-T.23S.-R.16E.
4649 feet from south section line
5012 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: STATE OF KANSAS
Name & FEE FUND PLUGGING
Address _____

Lease/Well# SUTHERLAND NO.1
County WOODSON
Well Total Depth 1000' feet
Production Pipe: 2" Size Feet 1025'
Surface Casing: 7" Size Feet 40'
AB oil well Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE,LLC Lic. # 30670
Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: _____ Month: 10 2002

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO 1025' THAT HAD BEEN CEMENTED
IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH
OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part _____
TECHNICIAN
None _____

Operations Completed: Hour: 12:00P.M. Day: _____ Month: 10 2002

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 1025'. CEMENT
WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT
SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.
A 2" PACKER WAS SET IN THE TOP OF THE CASING. CEMENT WAS THEN PUMPED
THROUGH THE PACKER INTO THE WELL UNTIL THE WELL WOULD PRESSURE. THE WELL
WAS THEN SHUT IN AT 200P.S.I.: 75 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: Control # 20030025-001
(If additional description is necessary, use BAC of this form.)

I DID observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

RECEIVED
OCT 21 2002
KCC WICHITA