

3021086

7-12

R 8

TO:

STATE CORPORATION COMMISSION

CONSERVATION DIVISION - PLUGGING SECTION

WICHITA STATE OFFICE BLDG., 130 S. MARKET, ROOM 2078

WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE #

101

OPERATOR: STATE OF KANSAS

NAME AND FEE FUND PLUGGING

ADDRESS

ABANDONED OIL WELL ☒ GAS WELL ☐ INPUT WELL ☐ SWD WELL ☐ D/A ☐

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR FAITH DRILLING COMPANY

LICENSE NUMBER 6023

ADDRESS P.O. BOX 816, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 11 MONTH: 7 YEAR: 95

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION

(PHONE) 316-431-6946

WERE: THIS WELL CONSISTED-PROBABLY OF AN APPROXIMATELY 8" BORE FROM WHICH THE CASING HAD BEEN REMOVED.

1" PIPE WAS RAN TO 850' AT WHICH DEPTH AN OBSTRUCTION WAS ENCOUNTERED. THE PLUGGING PROPOSAL WAS TO PLACE
50 SACKS OF CEMENT AT 850' AND FILL THE WELL WITH CEMENT FROM 350' TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY CLAYTON P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL ☒ PART ☐ NONE ☐

OPERATIONS COMPLETED: HOUR: 1:00 PM DAY: 12 MONTH: 7 YEAR: 95

ACTUAL PLUGGING REPORT 1" PIPE WAS RAN INTO THE WELL TO 850'. AT 850' AN OBSTRUCTION WAS ENCOUNTERED.

2 SACKS OF GEL WERE PUMPED INTO THE 1" PIPE TO 850'. 50 SACKS OF CEMENT WERE THEN PUMPED THROUGH THE
1" PIPE TO 850'. THE 1" PIPE WAS PULLED TO 350'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT

CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. SETTLEGE AND DISPLACEMENT WERE
FILLED FROM SURFACE. CEMENT WAS PUMPED BY CONSOLIDATED INDUSTRIAL SERVICES, INC.

RECEIVED
STATE CORPORATION COMMISSION

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

CLAYTON P. TITEL
CONSERVATION DIVISION
WICHITA, KANSAS
(TECHNICIAN)

FORM CP-2/3

AUG 17 1995

TB