

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-151-22225-00-00  
Spot: SWSE Sec/Twnshp/Rge: 31-27S-11W  
684 feet from S Section Line, 2025 feet from E Section Line  
Lease Name: BERGNER Well #: 1-31  
County: PRATT Total Vertical Depth: 4393 feet

Operator License No.: 33989  
Op Name: BENGALIA LAND AND CATTLE COMP  
Address: PO BOX 521008  
TULSA, OK 74152

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4435	2400	WITH 185 SX CMT
SURF	13.375	295		WITH 325 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/05/2017 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK TO 4230' & 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 320' WITH 80 SX CMT. PLUG AT 40-0' WITH 40 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG  
Date/Time Plugging Completed: 01/05/2017 2:30 PM

WitnessType: COMPLETE (100%)  
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4220' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 320' WITH 80 SX CMT. 3RD PLUG AT 40' WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4302	4310		
4282	4294		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed Steve Pfeifer  
(TECHNICIAN)

RECEIVED  
JAN - 6 2017  
KCC DODGE CITY

Form CP-2/3

INVOICED

JAN 17 2017