

15-155-19039-000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

April 5, 1966

RECEIVED  
STATE CORPORATION COMMISSION  
APR 15 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Art Lamb of Lamb Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Fell & Wolfe Oil Company

Complete Address: P.O. Box 7447, Tulsa, Oklahoma

Lease Name: Snowbarger Well No. 1

Location: W/2 NE 1/4 Sec. 21 Twp. 23 Rge. 10 (W) X

County Reno Total Depth 3784' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Lamb was instructed to plug the well as follows:

Fill hole with sand to 3750' and cement with 5 sacks.

Fill hole with mud to 185'. Set rock bridge from 185' to 175' and

cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

  
Conservation Division Agent