

State of Kansas



15.083.30099.00.00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 27 1966

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Voth of Sunray DX Oil co. has this

date requested permission to plug the following described well:

Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: Sunray DX Oil Company

Complete Address: 300 Union Natl. Bldg., Wichita, Kansas

Lease Name: Nicholas Goebel Well No. 1

Location: C NE NE Sec. 26 Twp. 21 Rge. 24 (E) (W)

County Hodgeman Total Depth 4724' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Voth was instructed to plug the well as follows:

8 5/8" to 324' Circulated w/ cement. 5 1/2" to 4723' Cemented

Plug bottom w/ 20 sacks cement. Top of cement 4520'

Mud 4520' to 375' 10 sacks of mud, Haliburton Plug,

35 sacks cement, 4 sacks of mud & 10 sacks of cement 375' to 0'

Pump.

Very truly yours,

*Edgar J. Lives*  
Conservation Division Agent