



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

OCT 30 1963

CONSERVATION DIVISION
 Wichita, Kansas

10-30-1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Burton of PICKRELL Drilling Co. has this

date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: PICKRELL Drilling Co.

Complete Address: 705 4th. National Bk, Bldg. Wichita, Kansas

Lease Name: Rankin Well No. 1

Location: C SW NE Sec. 13 Twp. 21S Rge. 24 (E) (W)

County Hodgeman Total Depth 4577' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burton was instructed to plug the well as follows:

8 5/8" - 315' Circulated w/cement.

Mud 4577' to 700' Spotted 25 Sax.cement 700' to 625'

Mud 625' to 300' Spotted 25 Sax.cement 300' to 225'

Mud 225' to 40' Plug,Hulls,15 Sax.cement 40' to 0

Very truly yours,

[Signature]
 Conservation Division Agent