

State of Kansas



15.083.20079.00.00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 29 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Buffington of William H. Pine has this  
date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: William H. Pine Opr.

Complete Address: Mc Culloch Bldg., Okmulgee, Oklahoma

Lease Name: Wilma Well No. 1

Location: C SE NW Sec. 7 Twp. 21 Rge. 24 (E) (W)

County Hodgeman Total Depth 4427' Oil Well X

Gas Well X Input Well      SWD Well      D & A X Lost Hole     

Mr. Buffington was instructed to plug the well as follows:

8 5/8" to 250' circulated w/ cement. Mud 4427' to 700'

Spot 80 sacks cement 700' to 400' Mud 400' to 250'

Spot 30 sacks cement 250' to 150' Mud 150' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar Eves  
Conservation Division Agent