

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

JUN 28 1971

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM

(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Boughner of Pet Inc. has this

date requested permission to plug the following described well:

Mr. Boughner guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 200 W. Douglas, Wichita, Kansas

Lease Name: Bamberger "C" Well No. 1

Location: C SE NE Sec. 26 Twp. 21 Rge. 23 (E) (W)

County: Hodgeman Total Depth 4595' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Boughner was instructed to plug the well as follows:


8 5/8" to 350' circulated w/ cement. Mud 4595' to 800'

Spot 80 sacks cement 800' to 500'. Mud 500' to 350'

Spot 30 sacks cement 350' to 250' Mud 250' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent