

State of Kansas



15.083.10210.00.00

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Comstock of Misco Leasing Inc. has this

date requested permission to plug the following described well:

Mr. Comstock guarantees payment of the plugging fee.

Operator's full Name: Misco Leasing Inc.

Complete Address: 101 Misco Bldg., Wichita, Kansas

Lease Name: Weiland "A" Well No. 2

Location: C NE SW Sec. 16 Twp. 21 Rge. 22 (E) (W)

County Hodgeman Total Depth 4450' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Comstock was instructed to plug the well as follows:

8 5/8" to 273' circulated w/ cement. 4 1/2" to 4441' cemented.

Top perforations 4284' Bottom plugged to 700' w/ sand.

Plug & 50 sacks cement 688' to 500' Mud 500' to 350'

100 sacks cement 350' to 0'

Very truly yours,

Conservation Division Agent