



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 3 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Grubbs of Colorado Oil & Gas Corporation on this date requested permission to plug the following described well:

Mr. Grubbs guarantees payment of the plugging fee.

Operator's full Name: Colorado Oil & Gas Corporation

Complete Address: Box 1030 Wichita, Kansas

Lease Name: Foreman Well No. A-1

Location: C SW NW Sec. 5 Twp. 21S Rge. 21 (E) (W)

County Hodgeman Total Depth 4485' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Grubbs was instructed to plug the well as follows:

8 5/8"-286 1/2" Circulated w/cement.

Mud 4485' to 600' 25 Sax. cement spotted at 600' to 500'

Mud 500' to 275' 25 Sax. cement spotted at 275' to 200'

Mud 200' to 40' Plug, Hulls, 15 Sax. cement 40' to surface.

Weld plate on surface pipe.

Very truly yours,

Hugh Scott
 Conservation Division Agent