

STATE OF KANSAS  
STATE CORPORATION COMMISSION

15.083.00010.00.00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Hodgeman County. Sec. 28 Twp. 21S Rge. 21 (X) (W)

Location as "NE/CNW/SW" or footage from lines C SE NE

Lease Owner Herman Geo. Kaiser

Lease Name Eakin Well No. 1

Office Address 909 Palace Building, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 3, 19 61

Application for plugging filed March 3, 19 61

Application for plugging approved March 3, 19 61

Plugging commenced March 3, 19 61

Plugging completed March 3, 19 61

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle A. Rives

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,351 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 237'   | None       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with rotary mud to 220 feet. Set plug and cemented with hulls and 20 sacks cement through drill pipe. Mudded hole to 35 feet. Set plug and cemented with 10 sacks cement.

3-8-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.

Address 709 Petroleum Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick  
L. C. Sponenberg (employee of owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg

709 Petroleum Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of March, 19 61

Geraldine Hays  
Geraldine Hays, Notary Public.

My commission expires December 3, 1964.




KANSAS GEOLOGICAL SOCIETY 15.083.000/0.00.00  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Herman Geo. Kaiser**  
 FARM **Eakin** NO. **1**

SEC. **28** T. **21S** R. **21W**  
 LOC. **C SE NE**

TOTAL DEPTH **4,351'**  
 COMM. **2-17-61** COMP. **3-3-61**  
 SHOT OR TREATED  
 CONTRACTOR **H-90, Inc.**  
 ISSUED

COUNTY **Hedgeman,**  
 KANSAS



CASING  
 20 10  
 15 8 **5/8" 237' cen. w/125. ex**  
 12 6  
 13 5

ELEVATION **2120 GR**  
**2191 DF**  
**2134 NG**  
 PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

|                         |      |
|-------------------------|------|
| Soil, sand & shale      | 237  |
| Shale & shells          | 415  |
| Red Bed, Shale & Shells | 620  |
| Anhydrite               | 640  |
| Red Bed, Shale & Shells | 720  |
| Sand                    | 850  |
| Red Bed, Shale & Sand   | 905  |
| Red Bed & Shale         | 1040 |
| Red Bed & Shells        | 1275 |
| Anhydrite               | 1305 |
| Red Bed & Shale         | 1370 |
| Shale & Red Bed         | 1680 |
| Shale & Lime            | 2120 |
| Lime & Shale            | 2455 |
| Lime                    | 2525 |
| Lime & Shale            | 2600 |
| Shale & Lime            | 3920 |
| Lime & Shale            | 3595 |
| Chalky Lime & Shale     | 3600 |
| Lime & Shale            | 3725 |
| Lime                    | 4198 |
| Lime & Shale            | 4250 |
| Lime                    | 4300 |
| Lime & Chert            | 4331 |
| Mississippi             | 4351 |
| R. T. D.                | 4351 |

REGISTERED  
 STATE COMMISSION  
 3 1964  
 CONSERVATION DIVISION  
 Wichita, Kansas

Top

|                |      |       |
|----------------|------|-------|
| Anhydrite Top  | 1275 | + 859 |
| Anhydrite Base | 1305 | + 829 |
| Topoka         | 3270 | -1105 |
| Heebner        | 3663 | -1535 |
| Toronto        | 3687 | -1553 |
| Lansing        | 3725 | -1591 |
| Case K.C.      | 4100 | -1966 |
| Narvata        | 4120 | -1986 |
| Charokee       | 4201 | -2067 |
| Mississippi    | 4318 | -2184 |
| R. T. D.       | 4351 | -2217 |

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-90, Inc.

*L. C. Sporenberg*  
 L. C. Sporenberg

STATE OF KANSAS )  
 ) SS:  
 SEDGWICK COUNTY )

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 7th day of March, 1961.

*Geraldine Hays*  
 Geraldine Hays, Notary Public

My Commission Expires:  
 December 3, 1964.