

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.083.21143.00.00

API NUMBER _____

LEASE NAME Rodney #1

WELL NUMBER _____

SPOT LOCATION SW SW SW

SEC. 14 TWP. 21 SRGE. 21 W(E) or (W)

COUNTY Hodgeman

Date Well Completed _____

Plugging Commenced 2/20/85

Plugging Completed 2/27/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kelso Casing bought f/ 3 Bar, Inc.

ADDRESS Box 139, 2015 Forest, Great Bend, Ks. 67530

PHONE # (316) 792-3535 OPERATORS LICENSE NO. _____

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4370'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1291'	none
				5 1/2"	4368'	2846'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 4265' & 5 sacks cement. Shot pipe at 3507', 3300', pulled 17 joints of pipe. Pipe hung up in hole. Shot pipe at 2470' & 2147'. Pulled 52 more joints. Plugged well with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, & 125 sacks 60/40 poz 2% gel 3% c.c. Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling
Address Box 347, Chase, Ks. 67524

License No. REC6050.D
STATE CORPORATION COMMISSION

MAR 04 1985

STATE OF Kansas COUNTY OF Rice, ss.

CONSERVATION DIVISION
Wichita, Kansas


R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

3-4-85

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 1st day of March, 1985



Irene Hoover
Notary Public

My Commission expires: _____