

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-083-21,162 ^{CO}

LEASE NAME DAVIDSON ^{CO}

WELL NUMBER 1

SPOT LOCATION SW SE NE

SEC. 7 TWP. 21S RGE. 24W (NW)

COUNTY Hodgeman

Date Well Completed 10-1-84

Plugging Commenced 9-30-84

Plugging Completed 10-1-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Advanced Recovery Services

ADDRESS P. O. Box 5351,
Englewood, CO 80155

PHONE # (303) 790-0252 OPERATORS LICENSE NO. 9755

Character of Well Dry
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4472

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface	Shale	0	305	8-5/8"	301	none
cemented with 250 sx 60/40 posmix, 2% gel, 3% cc, plug down at 8:30 p.m. 9-23-84 by Sun; cement did circ.						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged as follows with 60/40 posmix 2% gel, 3% cc by Sun plug down 12:30 a.m. 10-1-84

15 sx in rat hole; 50 sx @ 1520'; 60 sx @ 750'; 50 sx @ 350'
10 sx @ 40' w/solid bridge plug

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor J. W. Drilling Co., Inc. License No. 5137
Address 200 E. First, Suite 500
Wichita, KS 67202

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


Jon T. Williams, Jr.

(employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jon T. Williams, Jr.

(Address) 200 E. First, Suite 500
Wichita, KS 67202

OCT 09 1984
10-9-84
CONSERVATION DIVISION
Wichita, Kansas



SUBSCRIBED AND SWORN TO before me this 1st day of October, 1984

Geraldine Stewart
Notary Public

My Commission expires: January 14, 1985