

STATE OF KANSAS
STATE CORPORATION COMMISSION

15.081.10219.00.00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH

X			

Locate well correctly on above
Section Plat

Haskell County. Sec. 16 Twp. 30S Rge. 34 (E) W (W)
Location as "NE/CNW/SWK" or footage from lines C-NW-SW
Lease Owner United Producing Company, Inc.
Lease Name J.C. Stevens Well No. 4
Office Address Drawer 30, Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dryhole
Date well completed 1-5 1958
Application for plugging filed May 12 1959
Application for plugging approved May 13 1959
Plugging commenced June 5 1959
Plugging completed June 5 1959
Reason for abandonment of well or producing formation Dryhole

If a producing well is abandoned, date of last production - 19-
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives
Producing formation Dryhole Depth to top _____ Bottom _____ Total Depth of Well 6 071 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1 775	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with heavy mud to 2 900', spot cement from 2 900' to 2 500', heavy mud to 600', spot 20 sacks cement, mud to 20', pumped cement to base of cellar.

RECEIVED
STATE COMMISSION
JUN 9 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor United Producing Company, Inc.
Address Drawer 30, Liberal, Kansas (Halliburton)

STATE OF KANSAS, COUNTY OF SEWARD, ss.
L.S. BROWN (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L.S. Brown
Drawer 30, Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of June, 1959

Lila J. Brewer
Notary Public.

My commission expires 1-30-60

PLUGGING
FILE SEC 16 T 30 R 34
BOOK PAGE 38 LINE 9

15.081.10219.00.00

J. C. STEVENS WELL NO. 4

Ctr. NW SW
Sec. 16-30S-34W
Haskell County, Kansas

CONTRACTOR: The R. W. Rine Drilling Co.

STARTED: December 12, 1957

COMPLETED: January 7, 1958

LOG

Surface, Clay & Sand	0	-	240
Red Bed & Shale	240	-	785
Red Bed & Sand	785	-	1074
Red Bed & Anhydrite	1074	-	1145
Red Bed, Anhydrite & Shale	1145	-	1405
Red Bed, Anhydrite & Sand	1405	-	2080
Shale & Anhydrite	2080	-	2350
Lime, Shale & Anhydrite	2350	-	2485
Lime & Shale	2485	-	2800
Lime	2800	-	2912
Lime & Shale	2912	-	3095
Lime	3095	-	3205
Lime & Shale	3205	-	3359
Lime	3359	-	3795
Lime & Shale	3795	-	4658
Lime	4658	-	5288
Lime, Shale & Sand	5288	-	5388
Shale & Lime	5388	-	5746
Chert, Lime & Shale	5746	-	5793
Chert & Lime	5793	-	5820
Lime	5820	-	5949
Lime & Chert	5949	-	5985
Lime, Chert & Dolomite	5985	-	6071
T.D.	-	-	6071

Syfo @ 800' 1 1/2°
 Syfo @ 1100' 1 1/2°

 Syfo @ 1770' 1/2°
 8-5/8" Csg. @ 1775' w/ 750 sx.
 Syfo @ 2070' 3/4°
 Syfo @ 2340' 1°

 Syfo @ 2750' 2 1/2°

 Syfo @ 2900' 1-3/4°
 Syfo @ 3100' 1 1/2°
 Syfo @ 3910' 1 1/2°
 Syfo @ 3690' 3/4°
 Syfo @ 3900' 0° @ 4200' 1 1/2°
 Syfo @ 4400' 1 1/2°
 Syfo @ 4700' 1/2° @ 4975' 1/2°
 Syfo @ 5260' 1°

 Syfo @ 5600' 1 1/2°

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

RECEIVED
STATE CORPORATE COMMISSION
MAY 13 1959
CONSERVATION DIVISION
Wichita, Kansas

I, R. M. Green, do hereby certify that the above is a true and accurate log of the J. C. Stevens No. 4, located Ctr. NW SW of Section 16-30S-34W, Haskell County, Kansas.


 Ass't Secretary and Treasurer

Subscribed and sworn to before me this 10th day of January, 1958.

PLUGGING			
FILE	SEC	T.	R.
	16	30	34W
BOOK	PAGE	LINE	
	38	9	



My commission expires: 6/14/58