


STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 Give All Information Completely  
 Make Required Affidavit  
 Mail or Deliver Report to:  
 Conservation Division  
 State Corporation Commission  
 211 No. Broadway  
 Wichita, Kansas

15.083.00280.00.00  
 WELL PLUGGING RECORD

Form CP-4



Locate well correctly on above  
 Section Plat

Hodgeman County. Sec. 5 Twp. 21S Rge. 21W (E) (W)  
 Location as "NE/CNW/SW" or footage from lines C SW SW  
 Lease Owner Wilcox Oil Company  
 Lease Name BRITTIE Well No. 1  
 Office Address Box 1440, Tulsa, Oklahoma  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed 5-7 1964  
 Application for plugging filed 5-7 1964  
 Application for plugging approved 5-7 1964  
 Plugging commenced 5-7 1964  
 Plugging completed 5-7 1964  
 Reason for abandonment of well or producing formation no oil or gas found  
in commercial quantities.  
 If a producing well is abandoned, date of last production - - - 1964  
 Was permission obtained from the Conservation Division or its agents before plugging was com-  
 menced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott, Sublette, Kansas  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4396 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE  | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8-5/8 | 410    | None       |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set plug @ 700', spot 25 sacks cement. Filled hole with rotary mud to 400', set plug, spot 25 sacks cement. Filled hole with rotary mud to 45', set plug & hulls. Capped with 15 sacks cement. Plug down 9:20 p.m. 5-7-64.

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 13 1964

CONSERVATION DIVISION  
 WICHITA, KANSAS

3-13-64

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Rains & Williamson Oil Co.  
 Address 1425 Wichita Plaza, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Wilson Rains (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains  
Wilson Rains  
1425 Wichita Plaza, Wichita, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of May, 1964

My commission expires Jan. 8, 1968

Shirley Keck  
 Shirley Keck  
 Notary Public.

15.083.00280.00.00

Operator: Wilcox Oil Company  
NO. 1 BRITTIE  
C SW SW Sec. 5-21S-21W  
Hodgeman County, Kansas

Contractor: Rains & Williamson Oil Co.  
Commenced: 4-21-64  
Completed: 5-7-64

Remarks: Set 3-5/8" surface casing  
at 410' with 200 sacks  
cement.

Formations:

|                          |       |
|--------------------------|-------|
| Shale & Shells           | 90'   |
| Shale                    | 410'  |
| Shale & Red Bed          | 706'  |
| Lime                     | 713'  |
| Shale & Shells           | 800'  |
| Sand                     | 990'  |
| Shale & Red Bed          | 1345' |
| Anhydrite                | 1373' |
| Shale & Shells           | 1590' |
| Shale & Lime             | 2170' |
| Lime                     | 2203' |
| Lime & Shale             | 2871' |
| Sand                     | 2896' |
| Lime                     | 2910' |
| Lime & Shale             | 3490' |
| Lime                     | 4396' |
| Rotary Total Depth (D&A) | 4396' |

We certify the above log is true  
and correct to the best of our  
knowledge and belief.

RAINS & WILLIAMSON OIL CO.

*Wilson Rains*  
Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the  
State of Kansas, County of Sedgwick, this 11th day of May, 1964.

My Commission Expires:  
January 8, 1968

*Shirley Keck*  
Shirley Keck, Notary Public  
STATE CORPORATION COMMISSION

MAY 13 1964

CONSERVATION DIVISION  
Wichita, Kansas