

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

10040


15.083. ~~10042~~.00.00

WELL PLUGGING RECORD

Hodgeman County, Sec. 5 Twp. 21S Rge. 21W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SW NW
Lease Owner Colorado Oil & Gas Corporation
Lease Name FOREMAN A Well No. 1
Office Address Denver Club Building, Denver, Colorado
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 29, 1963
Application for plugging filed August 29, 1963
Application for plugging approved August 29, 1963
Plugging commenced August 30, 1963
Plugging completed August 30, 1963
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4485 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRM	TO	SIZE	PUT IN	PULLED OUT
Post Rock & Shale	Surface Casing	-0-	286 1/2'	8-5/8"	286 1/2'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged Hole: Filled hole w/ heavy mud from 4485' up to 600'. Spotted 25 sx. cement through drill pipe by Sun Cement Co. Filled hole with mud up to 275'. Spotted 25 sx. cement through drill pipe. Filled hole with mud up to 40', 1/2 sk. bulls, Sun plug, 15 sx. cement to cellar zero. Job done by Sun Cementing Co.

Job completed: 12:15 a.m. August 30, 1963.

RECEIVED
STATE CORPORATION COMMISSION

SEP 4 1963

CONSERVATION DIVISION
Wichita, Kansas

9-4-63

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SIERRA PETROLEUM CO., INC.
Address 208 Petroleum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. T. HONAKER, DRLG. SUPT. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker C. T. HONAKER, DRLG SUPT
Box 232, Russell, Kansas

SUBSCRIBED AND SWORN TO before me this 3rd day of September, 1963

(Address)

My commission expires 10-17-63

Leroy Dietz
Notary Public.



15.083.10040.00.CO

COLORADO OIL & GAS CORP. - Operator

SIERRA PETRO. CO., INC. - Contractor

FOREMAN A-1
C SW NW
Sec. 5-21S-21W
Hodgeman County, Kansas

T. D.: 4485'

Commenced: 8-15-63
Completed: 8-28-63

Casing:
8-5/8" Set at 286.50'

Cement:
with 200 sx. Sunset

FORMATION

DEPTH

Post Rock & Shale
Shale
Sand
Shale
Red Bed & Shale
Lime
Shale & Red Bed
Sand
Red Bed, Shale & Sand
Shale & Shells
Shale & Lime
Lime & Shale
Lime
Chert
Chert & Lime

130
320
380
555
745
757
845
1060
1390
2055
2130
3795
4390
4427
4485

RECEIVED
STATE CORPORATION COMMISSION

SEP 4 1963

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. T. Honaker
Drilling Superintendent

Subscribed and sworn to before me this 3rd day of September, 1963.

LeRoy Dietz
Notary Public

My commission expires: 10-17-63