


15.083.10124.00.00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

All Information Completely  
Required Affidavit  
or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Hodgeman County, Sec. 8 Twp. 21S Rge. 21S (X) (W)  
Location as "NE/CNW/SW" or footage from lines C SW NE  
Lease Owner Herman George Kaiser, Oil Producer  
Lease Name Mooney Well No. 1  
Office Address 909 Palace Building, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-17-63 19  
Application for plugging filed 5-17-63 19  
Application for plugging approved 5-17-63 19  
Plugging commenced 5-17-63 19  
Plugging completed 5-17-63 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4420 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	263'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 22 1963

CONSERVATION DIVISION  
Wichita, Kansas

Mud to 550', 1/2 sack hulls, Plug, 20 sacks cement  
Mud to 240', 1/2 sack hulls, Plug, 20 sacks cement  
Mud to 40', 1/2 sack hulls, Plug, 10 sacks cement to bottom of cellar  
2 sacks in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address P. O. Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite  
P. O. Box 486, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of May, 1963

My commission expires April 1, 1967  
Ulanda Nichols Notary Public.

15.083-10124.00.00

DRILLER'S LOG

COMPANY: Herman George Kaiser, Oil Producer  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: MOONEY #1  
 LOCATION: C SW NE Sec. 8-21S-21W  
 HODGEMAN COUNTY, KANSAS  
 COMMENCED: 5-7-63  
 COMPLETED: 5-17-63

0	263	Clay, Sand, Shale, Shells
263	570	Shale, Sand
570	675	Redbed
675	690	Gypsum
690	705	Redbed, Sand
705	950	Sand
950	1310	Redbed, Shale
1310	1340	Anhydrite
1340	1360	Redbed, Shale
1360	1600	Redbed, Shale, Shells
1600	1700	Shale, Lime Streaks
1700	2250	Shale, Lime
2250	2895	Lime, Shale
2895	3045	Shale, Lime
3045	3691	Lime, Shale
3691	4290	Lime
4290	4330	Lime, Chert
4330	4365	Chert, Lime
4365	4420	Chert
	<u>4420</u>	<u>Rotary Total Depth - D. &amp; A.</u>

RECEIVED  
STATE CORPORATION

MAY 22 1963

CONSERVATION D  
Wichita, Kansas

Set 8 5/8" used surface casing @ 263' Cemented with 200 sacks Sunset.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Mooney #1, located C SW NE of Section 8, Township 21 South, Range 21 West, Hodgeman County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS )  
                          ) SS  
COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 20th day of May, 1963.

Ulanda Nichols

Ulanda Nichols, Notary Public

My Commission Expires:  
April 1, 1967