


STATE OF KANSAS
STATE CORPORATION COMMISSION

15.083.10321.00.00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Hodgeman County. Sec. 9 Twp. 21S Rge. (E) 22 (W)
Location as "NE/CNW/SW" or footage from lines C SE/4 SW/4
Lease Owner J. H. Vandebark
Lease Name Cox Well No. 1
Office Address 826 SE Riverside Drive, Evansville 13, Indiana
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 12, 1960
Application for plugging filed May 12, 1960
Application for plugging approved May 12, 1960
Plugging commenced May 12, 1960
Plugging completed May 12, 1960
Reason for abandonment of well or producing formation



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot
Producing formation Depth to top Bottom Total Depth of Well 4400 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud from 4400' to 200'. Set Plug No. 1 at 200' with 1/2 sack hulls and 20 sacks cement. Filled hole with mud to 30'. Set Plug No. 2 at 30' with 10 sacks cement. Filled hole with cement to bottom of cellar. Put two sacks cement in rat hole. Plugging completed at 4:30 p.m. May 12, 1960.

RECEIVED
STATE CORPORATION COMMISSION

MAY 19 1960

CONSERVATION DIVISION
Wichita, Kansas

5-19-60

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Barnett Drilling, Inc.
Address 409 First National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jack S. Griggs (employee of owner, contractor or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack S. Griggs
409 First Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of May 1960

My commission expires November 26, 1962. Notary Public.



15.083.10321.00.00

BARNETT DRILLING, INC.
LOG OF COX NO. 1
C SE/4 SW/4, SEC. 9-21S-22W
HODGEMAN COUNTY, KANSAS

Commenced: 5/2/60

Completed: 5/12/60

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay	0	20	Ran 218' of 8-5/8" 28# Used Casing; cemented w/135 sax HA-5
Shale & Shells	20	70	
Sand	70	85	
Shale & Shells	85	216	
Shale	216	240	
Sand	240	285	
Shale	285	320	
Shale & Sand	320	540	
Shale, Shells & Red Bed	540	770	
Anhydrite?	770	793	
Shale & Shells	793	850	
Sand	850	1100	
Shale & Shells	1100	1240	
Sand & Shale	1240	1280	
Shale & Red Bed	1280	1424	
Anhydrite	1424	1461	
Shale & Shells	1461	2415	
Lime & Shale	2415	3965	
Lime	3965	4400'	T.D. D&A

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1960
CONSERVATION DIVISION
Wichita, Kansas

I, Jack S. Griggs, of Barnett Drilling, Inc. certify to the best of my knowledge and belief that the foregoing is a true and correct log of the Cox No. 1, located in the C SE/4 SW/4 of Section 9-21S-22W, Hodgeman County, Kansas.

Jack S. Griggs

Subscribed and sworn to by and before me in and for the County of Sedgwick, State of Kansas on this 3rd day of June, 1960.

Louise K. Whitted
Louise K. Whitted - Notary Public

My Commission expires November 26, 1962.

