


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15.083.10322.00.00  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Hodgeman County. Sec. 16 Twp. 21S Rge. (E) 22 (W)  
Location as "NE/CNW/SW" or footage from lines C NW/4 NW/4  
Lease Owner J. H. Vandembark  
Lease Name Wieland Well No. 3  
Office Address 826 SE Riverside Drive, Evansville 13, Indiana  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 30, 19 60  
Application for plugging filed May 30, 19 60  
Application for plugging approved May 30, 19 60  
Plugging commenced May 30, 19 60  
Plugging completed May 30, 19 60  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot  
Producing formation Depth to top Bottom Total Depth of Well 4407 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud from 4407' to 300'. Set Plug No. 1 @ 300' with 20 sacks cement. Filled hole with mud to 30'. Set Plug No. 2 @ 30' with 10 sacks cement. Filled hole with cement to bottom of cellar. Put three sacks cement in rat hole. Plugging completed at 5:00 A.M. May 30, 1960

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 1 1960  
CONSERVATION DIVISION  
Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Barnett Drilling, Inc.  
Address 409 First National Bank Bldg., Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK  
Jack S. Griggs (employee of owner, contractor or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack S. Griggs  
409 First Nat'l Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of May, 19 60  
Louise F. Whitfield  
Notary Public.

My commission expires November 26, 1962.



15.083.10322.00.00

BARNETT DRILLING, INC.  
LOG OF WIELAND NO. 3  
C NW/4 NW/4, SEC. 16-21-22W  
HODGEMAN COUNTY, KANSAS

Commenced: 5/17/60

Completed: 5/30/60

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay	0	20	Ran 316' of 8-5/8" 28# Used Casing; cemented w/200 sax HA-5
Shale & Shells	20	93	
Sand & Shale	93	130	
Shale & Shells	130	316	
Shale	316	550	
Shale & Red Bed	550	768	
Anhydrite	768	795	
Shale & Shells	795	850	
Sand	850	1095	
Shale	1095	1240	
Sand & Shale	1240	1290	
Shale & Red Bed	1290	1413	
Anhydrite	1413	1447	
Shale & Shells	1447	1885	
Shale	1885	2205	
Shale & Lime	2205	2505	
Lime & Shale	2505	3270	
Shale & Lime	3270	3415	
Lime & Shale	3415	3523	
Lime	3523	3615	
Lime & Shale	3615	3850	
Lime	3850	4407' T.D.	D&A

RECEIVED  
STATE CORPORATION COMMISSION

JUN 27 1960

CONSERVATION DIVISION  
Wichita, Kansas

I, Jack S. Griggs, of Barnett Drilling, Inc. certify to the best of my knowledge and belief that the foregoing is a true and correct log of the Wieland No. 3, located in the C NW/4 NW/4 of Section 16-21-22W, Hodgeman County, Kansas.

*Jack S. Griggs*

Subscribed and sworn to by and before me in and for the County of Sedgwick, State of Kansas on this 31st day of May, 1960.

*Louise K. Whitted*  
Louise K. Whitted - Notary Public

My Commission expires November 26, 1962.