


WELL PLUGGING RECORD

All information completely
Required Affidavit
or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Hodgeman County. Sec. 1 Twp. 21S Rge. 23 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C-NE-NW

Lease Owner Terrel Drilling & Producing

Lease Name Waterhouse Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 2-15 19 63

Application for plugging filed 2-14 19 63

Application for plugging approved 2-14 19 63

Plugging commenced 2-14 19 63

Plugging completed 2-15 19 63

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 4588 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	156	8 5/8	156	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 300', plug, 1/2 sack hulls and 20 sacks cement.

Filled hole with mud to 150', plug, 1/2 sack hulls and 20 sacks cement.

Filled hole with mud to 30', plug, 1/2 sack hulls and 10 sacks cement.

Job complete @ 2:00 A. M. 2-15-63

RECEIVED
STATE CORPORATION COMMISSION

FEB 25 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Terrel Drilling & Producing

Address Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

Joe K. Branum (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe K. Branum

Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of February, 19 63

My commission expires November 13, 1963.

Mary Anna Branum
Notary Public.

15.083-10327.00.00

RECEIVED
STATE CORPORATION COMMISSION

FEB 25 1963

W E L L L O G

CONSERVATION DIVISION
Wichita, Kansas

OPERATOR: Terrel Drilling & Producing
Russell, Kansas

CONTRACTOR: Company Tools

LEASE: Waterhouse # 1

COMMENCED: February 2, 1963

LOCATION: C-NE-NW, Sec. 1-21S-23W
Hodgeman County, Kansas

COMPLETED: February 15, 1963

FORMATIONS & DEPTHS

Surface Clay	20	Lime	2825
Sand & Shale	150	Lime & Shale	2960
Shale	670	Lime	3085
Sand & Shale	860	Lime & Shale	3985
Lime	880	Lime & Chalk	4051
Sand & Shale	1140	Lime & Chert	4100
Shale & Shells	1606	Lime	4450
Anhydrite	1640	Lime & Shale	4473
Shale & Shells	2255	Lime & Chert (R.T.D.)	4588
Lime & Shale	2635	Welox Log T.D.	4590

STATE OF KANSAS

COUNTY OF RUSSELL ss

Joe K. Branum, owner of Terrel Drilling and Producing, being first duly sworn on oath says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct.

Joe K. Branum
Joe K. Branum

Subscribed and sworn before me this 15th day of February, 1963.

Mary Anna Branum
Notary Public Russell County

My Commission Expires: November 13, 1963.