

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

15.083.00234.00.00  
WELL PLUGGING RECORD

NORTH R-23W

		Section 8	
X			

Locate well correctly on above Section Plat

Hodgeman County, Sec. 8 Twp. 21S Rge. 23W (E) (W)  
Location as "NE/CNW%SW%" or footage from lines C SW SW  
Lease Owner Tenneco Oil Company  
Lease Name Thomas G. Frusher Well No. 1  
Office Address P. O. Box 163 - Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry and Abandoned  
Date well completed July 18, 19 61  
T Application for plugging filed July 18, 19 61  
21 Application for plugging approved July 18, 19 61  
S Plugging commenced July 18, 19 61  
Plugging completed July 18, 19 61  
Reason for abandonment of well or producing formation Dry and Abandoned

If a producing well is abandoned, date of last production ----- 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8" OD	306'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set plug at 310' and cement with 20 sacks of cement, fill hole with mud. Set plug at 40' and cement with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 25 1961  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company  
Address P. O. Box 355, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Glen E. Armour (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glen E. Armour

(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of July, 19 61

John G. Lennon  
Notary Public.

My commission expires October 13, 1962

15.083.00234.00.00

# DRILLERS LOG

#1 Thomas G. Frusher

CASING RECORD: 313' of 8-5/8" surface casing  
 COMPANY: Tenneco Oil Company  
 DESCRIPTION: C/SW SW Section 8-21-23W  
 CONTRACTOR: Strata Drilling, Inc. Hodgeman Co., Kansas

TOTAL DEPTH: 4674'  
 COMMENCED: June 30, 1961  
 COMPLETED: July 18, 1961

D. & A.

FORMATION	FROM	TO	REMARKS
Shale & Sand	0	314	Ran 313' (10 Jts.) of 8-5/8" surface casing; set and cemented at 313' with 225 sacks of cement and 2% C. C. Plug down at 2:40 A. M. July 1, 1961.
Shale, Sand & Shells	314	850	
Red Bed	850	1000	
Sand	1000	1200	
Red Bed, Shale & Shells	1200	1540	
Anhydrite	1540	1585	
Shale	1585	1660	
Shale & Lime	1660	2095	
Shale	2095	2440	
Lime & Shale	2440	3881	
Lime	3881	4200	
Lime & Shale	4200	4285	
Lime	4285	4300	
Lime & Shale	4300	4360	
Lime	4360	4396	
Shale & Chert	4396	4465	
Lime & Chert	4465	4473	
Chert	4473	4638	
Chert & Lime	4638	4665	
Lost Circ.	4665	4674	

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 JUL 25 1961  
 CONSERVATION DIVISION  
 Wichita, Kansas

Total Depth 4674'

D. & A.

Plugged as follows: Set plug at 310' and cement with 20 sacks of cement, fill hole with mud. Set plug at 40' cement with 10 sacks cement. Plugged at 2:15 A. M., July 18, 1961.

STATE OF KANSAS )  
 ) SS:  
 COUNTY OF BARTON )

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

*Charles W. Steincamp*  
 Charles W. Steincamp, President

Subscribed and sworn to before me this 20th day of July, 1961.

*Robert E. Southern*  
 Notary Public Robert E. Southern

My commission expires:  
November 9, 1963