

15.083.00030.00.00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH 23-W

	29		
		X	

Locate well correctly on above
Section Plat

Hodgeman County. Sec. 29 Twp. 21-S Rge. (E) 23 (W)
Location as "NE/CNW%SW%" or footage from lines NW SE
Lease Owner Tennessee Gas Transmission Company
Lease Name Nettie E. Johnson Well No. 1
Office Address P. O. Box 163 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 13 19 60
Application for plugging filed July 13 19 60
Application for plugging approved July 15 19 60
Plugging commenced July 13 19 60
Plugging completed July 13 19 60
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division, or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4937 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TD	SIZE	PUT IN	PULLED OUT
				8-5/8"	404'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 360', set plug and hulls at 360', capped w/20 sacks cement. Mudded to 35', set plug and hulls at 35', 8 sacks cement to surface.

8-11-60

RECEIVED
STATE CORPORATION COMMISSION

AUG 11 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Glen E. Armour (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Glen E. Armour*

P. O. Box 163 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9 day of August 1960

My commission expires October 13, 1962

Notary Public.



COMPANY: **Tennessee Gas & Oil Company**
1120 Liberty National Bank Building
Oklahoma City 2, Oklahoma

LOCATION: **Johnson #1**
C-NW-SE Section 29-21S-23W
Hodgeman County, Kansas

Rotary Drilling Commenced **6-22-60**
 Rotary Drilling Completed **7-13-60**

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: **Ran 13 jts. 24# 8 5/8" casing. Set at 400'. Cemented with 300 sks.**
Cement circulated.
No Oil String - D & A

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

50	Clay	<u>Circulating for Samples</u>
70	Post Rock	2713'
160	Sandy Shale	2936'
402	Blue Shale	3050'
800	Shale	3120'
1000	Red Rock & Shale	3180'
1025	Anhydrite	3340'
1310	Sand, Red Rock & Shale	3372'
1600	Shale & Shells	3380'
1760	Shale & Lime	3424'
1900	Shale & Shells	3897'
2100	Shale & Lime	4372'
2310	Shale	4484'
3424	Lime & Shale	4569'
3530	Shale & Lime	4582'
3975	Lime & Shale	4610'
4473	Lime	4641'
4484	Cherokee Shale	4690'
4515	Lime	4793'
4560	Lime & k Shale	4829'
4582	Conglomerate	4862'
4641	Coring	4879'
4785	Mississippi	4937'
4891	Viola	
4937	Arbuckle	

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 11 1960
 CONSERVATION DIVISION
 Wichita, Kansas

Slope Tests

400	0°
1000	0°
1500	0°
2000	0°
2900	0°
3850	0°
4332	0°

S. M. L.: ---
 2467 OK
 4582 OK

The undersigned, Gerald W. Pike, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports:

PICKRELL DRILLING COMPANY
 By Gerald W. Pike
 Attorney-in-Fact
 Partner

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 19th day of July, 1960, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared Gerald W. Pike, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: September 24, 1962

Maxine Johnson
 Notary Public
 Maxine Johnson