


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Hodgeman County, Sec. 11 Twp. 21 Rge. (E) 24 (W)  
Location as "NE/CNWSWK" or footage from lines C SW SW  
Lease Owner MULL DRILLING COMPANY  
Lease Name Homer Hollenbeck Well No. 1  
Office Address 1625 Wichita Plaza, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 15, 19 63  
Application for plugging filed October 15, 19 63  
Application for plugging approved October 15, 19 63  
Plugging commenced October 15, 19 63  
Plugging completed October 15, 19 63  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation Depth to top Bottom Total Depth of Well 4520 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE  | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8 5/8 | 205    | None       |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 200'. Set plug. Cemented with  
25 sacks cement. Heavy mud to 40'. Set plug.  
Cemented with 15 sacks cement to bottom of  
cellar. Plugged rat hole with 2 sacks cement.

10-28-1963  
**RECEIVED**  
STATE CORPORATION COMMISSION

OCT 28 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor PICKRELL DRILLING COMPANY  
Address 705 4th National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
C. W. Sebitts

Of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
705 4th National Bnk Bldg, Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of October, 1963

My commission expires

June 21, 1966

Maxine Blackman

Notary Public.

15,083.10,56.00.00

ROTARY DRILLING LOG

COMPANY: MULL DRILLING COMPANY  
1625 Wichita Plaza  
Wichita, Kansas  
LOCATION: Homer Hollenbeck No. 1, C. SW SW 11-21-24,  
Hodgeman County, Kansas

Rotary Drilling Commenced 10-2-63  
Rotary Drilling Completed 10-15-63

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: (6 joints) 8 5/8" surface casing set at 205' cemented with 155  
sacks cement. Circulated. Completed 9:00 P.M. October 1, 1963.  
No oil string-run, D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

|      |                         |                    |
|------|-------------------------|--------------------|
| 85   | Post Rock & Clay        | <u>C. F. S.</u>    |
| 205  | Shale & Shells          | 4235               |
| 470  | Shale & Rock            | 4240               |
| 630  | Shale                   | 4341               |
| 905  | Red Rock                | 4352               |
| 925  | Blaine                  | 4413               |
| 995  | Red Beds, Shale, Shells | 4423               |
| 1200 | Sand                    | 4440               |
| 1525 | Red Bed, Shale & Shells | 4453               |
| 1565 | Anhydrite               | 4458               |
| 2185 | Shale & Shells          | 4468               |
| 2575 | Lime & Shale            | 4520               |
| 2795 | Lime                    |                    |
| 3441 | Lime & Shale            | <u>Slope Tests</u> |
| 3580 | Lime - Sandy Shale      | 2500               |
| 3645 | Lime & Shale            | 3000               |
| 3685 | Sandy Shale & Lime      | 3500               |
| 3746 | Sandy Shale             | 4000               |
| 3990 | Lime & Shale            |                    |
| 4425 | Lime                    | <u>S. L. M.</u>    |
| 4520 | Mississippian - TD      | 3369               |
|      |                         | 3734               |
|      |                         | 4147               |

**RECEIVED**  
STATE CORPORATION COMMISSION  
OCT 28 1963  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 18th day of October, 1963, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument, as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth:

Given under my hand and seal of office the day and year last above written.

Maxine Blackman  
Maxine Blackman Notary Public

My commission expires: June 21, 1966