


15.083.00039.00.00

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Hodgeman County, Sec 18 Twp. 21S Rge. 24W (E) (W)
 Location as "NE/CNW&SW" or footage from lines C SE NE
 Lease Owner Imperial Oil of Kansas, Inc.
 Lease Name Almquist Well No. 1
 Office Address 780 Fourth National Bldg., Wichita 2, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed March 18 19 60
 Application for plugging filed March 18 19 60
 Application for plugging approved March 18 19 60
 Plugging commenced March 18 19 60
 Plugging completed March 18 19 60
 Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot, St. John, Kansas
 Producing formation Depth to top Bottom Total Depth of Well 4510 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set first plug at 550' with 20 sacks of cement; set second plug at 310' with 20 sacks of cement; Set top plug at 40' with 10 sacks of cement.

4-20-60

RECEIVED
 STATE CORPORATION COMMISSION
 APR 20 1960
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Imperial Oil of Kansas, Inc.
 Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
 K. J. Boone (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) BY: K. J. Boone Pet. Engr.
 780 Fourth National Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 24th day of March, 19 60

Mona L. Latier

Notary Public.

My commission expires July 7, 1962

15.083.00039.00.00

DRILLER'S LOG

RECEIVED
STATE CORPORATION COMMISSION

APR 20 1960

CONSERVATION DIVISION
Wichita, Kansas

Imperial Oil of Kansas, Inc.
780 Fourth National Bldg.
Wichita 2, Kansas

Almquist #1
C SE NE Sec. 18-21S-24W
Hodgeman County, Kansas

Total Depth: 4510'

Elevation: 2318' K.B.
Production: D & A

Commenced: 3-1-60 Completed: 3-18-60

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 318' with 225 sacks of cement.

Figures indicate bottom of formations:

TOPS

Shale, Sand & Shells	930'	Heebner	3750'	(-1432)
Shale & Sand	1645'	Toronto	3772'	(-1454)
Shale	1950'	Lansing	3832'	(-1514)
Shale & Lime	3850'	Base Kansas City	4136'	(-1818)
Lime	4510'	Marm. Cherty Ls.	4262'	(-1944)
Total Depth	4510'	Cherokee shale	4310'	(-1992)
		Conglomerate	4383'	(-2065)
		Spergen	4408'	(-2090)
		Warsaw	4418'	(-2100)
		Osage	4453'	(-2135)
		Rotary Total Depth	4510'	(-2192)

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: K. J. Boone
K. J. Boone - Pet. Engr.

Subscribed and sworn to before me this 24th day of March, 1960.

My Commission Expires:

July 7, 1965

Mona L. Latier
Mona L. Latier - Notary Public