

15.083.30099.00.00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH

			X

Locate well correctly on above
Section Plat

Hodgeman County, Sec. 26 Twp. 21S Rge. 24W (E) (W)
Location as "NE/CNWKSWK" or footage from lines C - NE 1/4 - NE 1/4
Lease Owner Sunray DX Oil Company
Lease Name Nicholas Goebel Well No. 1
Office Address 300 Union National Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-23 19 66
Application for plugging filed 4-6 19 66
Application for plugging approved 4-7 19 66
Plugging commenced 5-20 19 66
Plugging completed 5-25 19 66
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. Eves, Box "F", Sublette, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4724 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUR IN	PULLED OUT
				8 5/8	324	-0-
				5 1/2	4724	3600

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

T.D. to 378' with mud laden fluid. Spot 35 sacks cement from 378' to 278'. Wooden plug from 278' to 277'. Mud laden fluid from 277' to 30'. Spot 10 sacks cement from 30' to surface.

RECEIVED
STATE CORPORATION COMMISSION

MAY 27 1966

5-27-66

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

V. A. Tracy

(employee of owner) or (SWANSON EXPERTS)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

300 Union National Building, Wichita

(Address)

Subscribed and Sworn to before me this 26th day of May, 19 66

My Commission Expires March 28, 1969

My commission expires

MAE RESCO
Notary Public.

PR-4

15.083 30099.00.00

STERLING DRILLING COMPANY
Sterling, Kansas

WELL LOG ----- NICHOLAS GOEBEL #1
LOCATED: C NE/4 NE/4 Section 26-21S-24W, Hodgeman County, Kansas

OWNER: Sunray DX Oil Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: March 3, 1966
COMPLETED: March 23, 1966

ROTARY TOTAL DEPTH: 4724'

LOG

0 - 80	Sand & Clay
80 - 300	Shale
300 - 870	Shale & Sand
870 - 1580	Anhydrite
1580 - 1714	Shale, Shells & Lime
1714 - 1975	Shale
1975 - 2775	Shale & Lime
2775 - 2895	Lime
2895 - 3810	Lime & Shale
3810 - 4065	Lime
4065 - 4127	Lime & Shale
4127 - 4227	Lime
4227 - 4284	Lime & Shale
4284 - 4345	Lime
4345 - 4385	Lime & Shale
4385 - 4450	Lime, Shale & Chalk
4450 - 4507	Lime
4507 - 4565	Lime & Shale
4565 - 4610	Lime
4610 - 4660	Lime & Chert
4660 - 4724	Lime T.D.

CASING RECORD

Ran 10 joints 8-5/8", 24# casing. 312' pipe set at 323' K.B. Cemented with 200 sacks #1 Pozmix, 3% HA-5. Plug was down at 4:00 a.m.

REC'D
STATE CORPORATION

APR 1966

CONSER
W...

Ran 146 joints 5-1/2" casing. 4724' pipe set at 4720' K.B., with 150 sacks Pozmix, 2% gel, with 5% CFR2, 250 gallons mud flush. Plug was down at 5:40 p.m. 3-23-66 by Halliburton.

RECEIVED
APR 20 1966
DECEIVED

888 03 9AM