

Locate well correctly on above Section Plat

Hodgeman County. Sec. 23 Twp. 21 Rge. ~~23~~ 24 (W)
 Location as "NE/CNW*SW*" or footage from lines. C SW SW
 Lease Owner Jones-Gebert Oil Co.
 Lease Name Goebel Well No. 1
 Office Address 1007 Central Building, Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed December 15, 1962 19
 Application for plugging filed December 15, 1962 19
 Application for plugging approved December 15, 1962 19
 Plugging commenced December 15, 1962 19
 Plugging completed December 15, 1962 19
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott, Liberal, Kansas
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4690 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	255'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug at 240' with 1/2 sack hulls and 35 Sacks cement. Set top plug at 40' with 14 sacks cement, 2 sacks cement in rat hole.

DEC 26 1962
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 WICHITA, KANSAS

12-26-62

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Jones-Gebert Oil, Inc.
 Address 1007 Central Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
 George R. Jones (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George R. Jones
 1007 Central Building, Wichita, Kansas
 (Address)

SUBSCRIBED AND SWORN to before me this 18th day of December, 19 62.

My commission expires February 1, 1964

Barbara J. Layton
 Barbara J. Layton Notary Public.

15.083.10119.00.00
DRILLERS' LOG

Company: Jones-Gebert Oil Co.
Contractor: Jones-Gebert Oil, Inc.
Farm: #1 Goebel, C SW SW
Sec. 23-21S-24W
Hodgeman Co., Kansas
Commenced: 12/3/62
Completed: 12/15/62
Casing: 8 5/8 @255' w/200 sx.

255 - 300	Lime and Shale
300 - 940	Lime and Shale
940 - 1365	Shale and Clay
1365 - 1490	Shale and Clay
1490 - 1580	Lime, Chert and Shale
1580 - 1705	Shale, Lime Streaks
1705 - 1915	Shale and Lime
1915 - 2205	Shale
2205 - 2395	Shale and Lime
2395 - 2515	Lime and Shale
2515 - 2610	Lime
2610 - 2670	Lime and Shale
2670 - 2785	Lime w/Shale
2785 - 2850	Lime w/Shale
2850 - 2915	Lime w/Shale
2915 - 3055	Shale and Lime
3055 - 3185	Shale and Lime
3185 - 3295	Shale and Lime
3295 - 3464	Shale w/Chalk streaks
3464 - 3609	Shale w/Chalk
3609 - 3781	Shale and Lime Streaks
3781 - 3881	Shale w/Chalk Streaks
3881 - 3895	Lime and Shale
3895 - 4023	Shale and Lime w/slight Chalk Streaks
4023 - 4118	Lime and Shale Streaks
4118 - 4133	Lime and Shale
4133 - 4180	Lime and Shale
4180 - 4235	Lime and Shale
4235 - 4270	Lime and Shale
4270 - 4337	Lime w/Shale Streaks
4337 - 4384	Lime
4384 - 4453	Lime and Shale
4453 - 4521	Lime and Shale
4521 - 4570	Lime and Shale
4570 - 4600	Lime and Shale
4600 - 4673	Mississippi
4673 - 4690	T.D.


DEC 26 1962
CONSERVATION
Wichita, Kansas

I, George R. Jones, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Goebel, C SW SW, Sec. 23-21S-24W, Hodgeman County, Kansas, as reflected by the files of the Jones-Gebert, Inc.


George R. Jones

State of Kansas - County of Sedgwick) ss:

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 18th day of December, 1962.


Barbara J. Layton, Notary Public

My Commission expires:
February 1, 1964.