

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

**Strike out upper line
when reporting plug-
ging off formations.**

Reno County, Sec. 27 Twp. 23 Rge. (E) 10 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 990' S and 330' E of N/4 Corner
Lease Owner. Cities Service Oil Co.
Lease Name. Essley Well No. 1
Office Address. Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed. 9-26 19. 47
Application for plugging filed. 9-26 19. 47
Application for plugging approved. 9-27 19. 47
Plugging commenced. 9-27 19. 47
Plugging completed. 9-27 19. 47
Reason for abandonment of well or producing formation. Dry Hole
If a producing well is abandoned, date of last production. 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well H. W. Kerr
Producing formation Viola LIME Depth to top 3805 Bottom 3808 Total Depth of Well 3808 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Heavy mud from	3808 ft. to 270'
Wood plug and 15 Sx. cement	270' to 225'
Heavy mud and soil	225' to 40'
10 sacks cement	40' to Base of cellar

10-10-47

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to..... V. M. Conover
Address..... Box 751
..... Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, SS.
V. M. Conover (employee of owner) or (~~owner or operator~~) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. J. Conner

SUBSCRIBED AND SWORN to before me this 1st day of October, 1947

My commission expires.....3-12-1951

21-548-g 8-45-6M

PLUGGING
FILE SEC 27 T 23 R 10W
BOOK PAGE 137 LINE 19

15-155-6980-0000

Company Citizens Service Oil Co. Well No. 1 Farm Kearney
 Location 900' South and 530' East of N/4 Corner Sec. 27 T. 23 R. 10W
 Elevation 1769 (1767 Gr.) County Kono State Kansas
 Drig. Comm. September 9, 1947 Contractor Corbett-Barbour Drilling Company
 Drig. Comp. September 26, 1947 Acid None
 T. D. 3003' Initial Prod. Dry Hole - P. & A. 9-27-47

CASING RECORD:

8-5/8" @ 272' cem. 208 sz cement

FORMATION RECORD:

shells & sand	0-70
sand & gravel	110
red bed	920
shale & shells	1030
salt	1035
salt & shale	1500
lime & shale	1475
lime	1570
lime & shale	1725
lime	3810
shale & lime	1920
broken lime	2050
shale & lime	2145
lime & shale	2250
shale & lime	2390
shale & lime shells	2430
shale & lime	2620
lime & shale	2800
shale & lime	2925
lime	3060
lime & shale	3116
shale & lime	3202
lime & shale	3250
shale	3293
lime	3416
lime & chert	3527
chert & lime	3664
shale	3697
chert & lime	3720
shale	3774
shale & lime	3803
shale	3805
lime	3808 T. D.

Top Lansing	3292'
Top Mississippi	3418'
Top Kinderhook	3663'
Top Viola	5505'
Penetration	3'
Total Depth	3808'

Drill stem test 3706-3808, recovered
 95" sulphur water in 30 minutes.

SLOPE TESTS (ACID BOTTLE):

1000'	OK
1850'	OK
1900'	OK
2050'	OK
2250'	OK
2750'	OK
3000'	OK
3500'	OK

PLUGGING
 FILE SEC 27 T 23 R 10W
 BOOK PAGE 137 LINE 12

