

15-155-02270-0000

STATE OF KANSAS CORPORATION COMMISSION

WELL PLUGGING RECORD


Give Information Completely. Make required Affidavit. Mail or Deliver Report to: Conservation Division, State Corporation Commission, 800 Pitting Building, Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Reno County, Sec. 30 Twp. 23 Rge. 10 (E) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. Lease Owner: Mid-Continent Petroleum Corporation. Lease Name: Opal Hartnett. Office Address: 512 Orpheum Bldg, Wichita, Kansas. Well No. 2. Character of Well: Oil & Gas. Date well completed: 1-10. Application for plugging filed: 3-11. Application for plugging approved: 3-15. Plugging commenced: 3-17. Plugging completed: 3-24. Reason for abandonment: Producing 2 1/2 Bbl of oil and 15 Bbl water daily. If a producing well is abandoned, date of last production: 3-8. Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well: Ruel Durkee, McPherson, Kansas. Producing formation: Viola Lime. Depth to top: 3653. Bottom: 3693. Total Depth of Well: 3693. Feet. Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Viola Lime, Oil & Gas, 3653', 3693', 7", 3673', 2979'. Row 2: 103/4, 235', None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to... feet for each plug set. Plugged with chat from 3693' to 3670'. Cemented with dump bailer from 3670' to 3640' with 6 sacks cement. Hole filled with heavy mud from 3640' to 230'. Rock bridge at 230'. Cemented from 230' to 190' with 20 sacks cement dumped with dump bailer. Heavy mud from 190' to 15'. Capped with 5 sacks cement from 15' to bottom of cellar. Cellar to be filled to ground level.

RECEIVED

Conservation Div.

APR 8 1950

4-8-50

STATE CORPORATION COMMISSION KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to R. L. Mankey. Address: 512 Orpheum Bldg, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct: So help me God.

(Signature)

R. L. Mankey

Ellinwood, Kansas RR#1

SUBSCRIBED AND SWORN to before me this 6th day of April, 1950

J. M. Sullivan

Notary Public.

My commission expires

16 June 1952

22-2625 2-48-15M

PLUGGING FILE SEC 30 T 23 R 104 BOOK PAGE 142 LINE 27

PLUGGING FILE SEC T R BOOK PAGE LINE

15-155-02270-0000

COMPANY - Mid-Continent Petroleum Corp.
FARM - Opal Hartnett No. 2

Sec. 30 T. 23S R. 10W
SW SW SE

Total Depth - 3693'
Comm. 12-15-44 Comp. 1-10-45
Shot or treated - 1000 acid
Contractor - Barnett Drilling Company

COUNTY - Reno

Elevation 1801 DF

Production 340 IP

CASING:
10 3/4" 32.75# L.W.New 235'
7" 24# S.H.S.S. 3673'

Surface clay & sand	0	110
Sand	110	150
Shale	150	190
Sand	190	210
Shale & shells	210	240
Shale	240	300
Red bed	300	360
Shale & shells	360	470
Sand & shale	470	475
Shale & shells	475	1450
Lime & shale	1450	1570
Shale	1570	1595
Lime & shale	1595	1635
Shale & shells	1635	1700
Lime	1700	2070
Broken lime	2070	2150
Shale	2150	2230
Shale & shells	2230	2710
Lime & shale	2710	2795
Shale	2795	2800
Lime	2800	3170
Lime & shale	3170	3240
Lime	3240	3280
Broken lime	3280	3290
Lime & shale	3290	3320
Lime	3320	3395
Sandy lime	3395	3400
Lime & shale	3400	3405
Lime	3405	3651
Sand (Misener)	3651	3653
Lime (Viola)	3653	3684
Lime	3684	3688
Lime, hard & cherty	3688	3690
Lime, very hard	3690	3691
Lime " "	3691	3692
Lime, softer	3692	3693
TOTAL DEPTH	3693	

APR 8 1950
RECORDS

PLUGGING
FILE SEC 30 T 23 R 10W
BOOK PAGE 142 LINE 27