

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


15-155-62268-0000

Company - HILL- MAN OIL CO., ET AL
Farm - Johnson Estate No. 1

SEC. 30 T. 23 R. 10 W
SW SE SW

Total Depth. 3713 $\frac{1}{2}$ '
Comm. 7-19-45 Comp. 8-1-45
Shot or Treated. 4000 gals. acid
Contractor.
Issued. 12-1-45

County. Reno
KANSAS



CASING:
8 5/8" 198' Cem.
5 1/2" 3703' Cem.

Elevation. _____

Production. Pot. 160 B.

Figures indicate Bottom of Formations.

sand	150
shale & shells	170
red rock	198
red rock & shale	765
red rock	1085
salt	1155
salt & shale	1225
shale & red bed	1440
lime & shale	1885
shale & shells	2185
shale & lime	2330
shale & shells	2420
lime brkn & shale	2425
lime, shale & shells	2530
lime & shale	2660
shale & shells	2695
lime & shale	2715
lime	2760
lime & shale	2805
lime	2900
shale	2940
lime	3270
lime & shale	3378
lime	3408
shale & lime strks	3475
lime	3662
lime & shale	3675
lime	3700
cherty lime	3706
lime	3713 $\frac{1}{2}$
Total Depth.	

7-12-48

Top of Viola 3680

5 1/2" casing cemented with 60 sax

Acidized w/4000 gals.
1800' oil 9 hrs. filled up
& flowed.

Deepening Record, with Cable tools.

By Francis M. Raymond.

Commenced 6/12/48, completed 6/18/48

From 3713 $\frac{1}{2}$ to 3768 Viola Lime, no oil, no water. 3768' new total depth.

Bottom of hole cemented with 10 sax cement, and 2 sax Calseal.

PLUGGING
FILE SEC 30 T 23 R 10 W
BOOK PAGE 31 LINE 3



of 10
10 5
5

(not to be used)

...

...

...

...