


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County, Sec. 16 Twp. 22S Rge. 16W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NW NW
Lease Owner: Christie-Stewart Drilling Co.
Lease Name: Kulz Well No. 1
Office Address: 611 Union Center
Character of Well (completed as Oil, Gas or Dry Hole) Non-productive
Date well completed: 4-18-63 1963
Application for plugging filed 4-18- 1963
Application for plugging approved 4-18- 1963
Plugging commenced 4-18 1963
Plugging completed 4-18 1963
Reason for abandonment of well or producing formation Non-productive

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3940 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	582'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud, spotted 4 sx hulls and 35 sx cement at 480'. Spotted 4 sx hulls and 15 sx cement 40' to top

RECEIVED
STATE CORPORATION COMMISSION

APR 23 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Company
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Robert C. Lewellyn (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert C. Lewellyn
611 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of April, 1963

My commission expires January 19, 1964. Patricia Hotmar Notary Public

INVOICED

DATE 4/23/63

INV. NO. 6250-2

WELL LOG

Company: Christie-Stewart Drilling Co. Sec: 16-225-16W
 Farm: Kulz Loc: SW NW NW
 RIG: No. 1 County: Pawnee
 Total Depth: 3940 State: Kansas
 Comm: 4-6-63 Comp: 4-18-63
 Contractor: Christie-Stewart Drilling Co. Elevation: 2024 KB
 Casing: 10 3/4" @-582 KBM/275 /sx Production: D&A

500'	Surf. soils, clays wtr sds.	3537'	Shale
1014'	Broken sd and sh.	3584'	Limestone
1040'	Anhydrite	3592'	Shale
1492'	Broken wtr sd.	3600'	Limestone
2005'	Broken hard limestone	3609'	Shale
2137'	Broken sand	3620'	Limestone
2277'	Sand	3636'	Shale
2531'	Broken wtr sd	3648'	Oolitic limestone
2669'	Sand	3680'	Shale
2925'	Broken sd and sh.	3687'	Limestone
3100'	Broken sd and limestone	3772'	Bkn Lmstn. & Sh.
3427'	Limestone and shale streaks	3804'	Shale
3447'	Shale	3858'	Limestone
3460'	Limestone	3883'	Cong
		3920'	Shale
		3940'	Dolomite
		3940'	TD

FORMATION TOPS

Heebner	3427	(-1403)
Brown Lime	3537	(-1513)
Lansing	3541	(-1517)
Base Kansas City	3772	(-1748)
Marmaton	3804	(-1780)
Conglomerate	3838	(-1814)
Simpson	3883	(-1859)
Arbuckle	3920	(-1896)
TD	3940	(-1916)