

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Pawnee County, Sec. 15 Twp. 22 Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines SW SW NE

Lease Owner Graham-Messman-Rinehart Oil Company

Lease Name Schartz Well No. 1

Office Address 1005 E. Second St., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 18, 19 53

Application for plugging filed April 18, 19 53

Application for plugging approved April 20, 19 53

Plugging commenced April 18, 19 53

Plugging completed April 18, 19 53

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives, Box 148, Pratt Co., Ks.

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4110 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	200	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud to 200'. Bottom Plug @ 200'  
w/25 sx. cement. Top plug @ 20'  
w/10 sx. cement. Mud to surface

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graham-Messman-Rinehart Oil Company

Address P. O. Box 1033, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

J. A. Gilliland (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland

P. O. Box 1033, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of April, 19 53

My commission expires December 1, 1956

B. A. Seal  
Notary Public.

PLUGGING  
FILE SEC 15 T 22 R 16 W  
BOOK PAGE 94 LINE 21

RECORDED  
INDEXED  
APR 22 1953  
CONSERVATION DIVISION  
Wichita, Kansas

SCHARTZ #1WELL RECORD

Location: SW SW NE, Sec. 15-22-16W  
Pawnee County, Kansas

Commenced: April 7, 1953

Completed: April 18, 1953

Operator: G-M-R Oil Company

Production: D & A

Contractor: G-M-R Drilling Co.

Elevation: 1939 K.B.

Gasing Record: 10-3/4" @ 200' w/150 sx. cement,  
4 gel., 2 C.C.'s

LOG

Sand & Shale	191
Shale	380
Sand	415
Shale & Red Bed	490
Shale & Red Bed	500
Sand	585
Shale & Shells	1035
Anhydrite	1060
Shale & Shells	1190
Shale & Red Bed	1400
Shale & Shells	1635
Shale & Shells	1915
Shale & Lime	2075
Lime	2185
Shale & Lime	2350
Lime & Shale	2450
Lime & Shale	2570
Lime & Shale	2720
Lime & Shale	2828
Lime & Shale	2960
Lime & Shale	3085
Lime & Shale	3185
Lime & Shale	3310
Lime & Shale	3385
Lime	3427
Lime	3480
Lime	3550
Lime & Shale	3620
Lime	3680
Lime	3745
Lime	3782
Lime	3825
Lime	3885
Lime	3930
Lime & Shale	3970
Lime & Shale	4009
Conglomerate	4040
Conglomerate	4075
Conglomerate	4080
Arbuckle	4110 T.D.

TOPS

1036 - Anhydrite (+1012)  
3628 - Brown Lime (-1580)  
3637 - Lansing (-1589)  
4045 - Simpson (-1997)  
4080 - Arbuckle (-2032)

The undersigned, GRAHAM-MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

GRAHAM-MESSMAN-RINEHART OIL COMPANY.

BY

*J. A. Gilliland*  
J. A. Gilliland

Subscribed and sworn to before me this 21st  
day of April, 1953.

*Bubba J. Scott*  
Notary Public

My Commission expires: December 1, 1956

**PLUGGING**

FILE SEC 15 T 22 R 16 W  
BOOK PAGE 24 LINE 21

CONSERVATION DIVISION  
Wichita, Kansas