

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

*Give All Information Completely
Make Required Affidavit
Mail Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County. Sec. 14 Twp. 22S Rge. 16 (X) W (W)

Location as "NE/CNW/SW" or footage from lines NW/4 NW/4 NW/4

Lease Owner Bell Oil & Gas Company

Lease Name Schar tz Well No. 1

Office Address Box 2007, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-24 19 56

Application for plugging filed 11-24 19 56

Application for plugging approved 11-24 19 56


Plugging commenced 11-24 19 56

Plugging completed 11-24 19 56

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well R. M. Brundege

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4110 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	356'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 346' with heavy drilling mud, set plug and cemented with 20 sacks cement. Filled hole to 40 ft. with heavy drilling mud, set plug and cemented to bottom of cellar with 10 sacks cement.

12-1-56

RECEIVED
STATE CORPORATION COMMISSION

DEC 1 - 1956

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation

Address 1516 Liberty Bank Building, Oklahoma City 2, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss. C. W. Dodson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Dodson
Oklahoma City, Oklahoma (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of November, 19 56

Carol Bradshaw
Notary Public.

My commission expires July 1, 1959

PLUGGING
FILE SEC. 14 T. 22 R. 16W
BOOK PAGE 119 LINE 18

CONTRACTOR'S WELL LOG

Bell Oil and Gas Company - Scharz No. 1 Well
 NW NW NW Section 14-22S-16W, Pawnee Co., Kansas

Total Depth: 4110
 Commenced: 11-10-56
 Completed: 11-24-56

Elevation: 2029' DF
 Casing: 8-5/8" @ 350'
 210 sacks pozmix

Formation	Depth
Clay, sand, shale	351
Redbed & Sand	500
Shell & Shale	1015
Anhydrite	1040
Shale & Shells	1400
Shale & Lime	2600
Shale & Shells	2725
Shale & Lime	3120
Lime	3185
Lime & Shale	3315
Lime	3393
Lime & Shale	3685
Lime	3794
Lime & Shale	3928
Shale	3968
Conglomerate	4036
Lime	4110 - Total Depth

I hereby certify the forgoing to be a true and correct Driller's Log to the best of my knowledge.

C. W. Dodson
 C. W. Dodson

Subscribed and sworn to before me this 29th day of November, 1956.

My commission expires:

July 1, 1959 RECEIVED STATE CORPORATION COMMISSION

Carol Binkshaw
 Notary Public

DEC 1 - 1956

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE NO. 14-22 R 16W
 BOOK NO. 119 PAGE 18