


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 13 Twp. 22S Rge. 16W (E) (W)
Location as "NE/CNW&SW" or footage from lines NE NE SW
Lease Owner Sterling Drilling Co, Anadarko Production Co & Martin Oil
Lease Name Fleske #1 & Gas Co. Well No. _____
Office Address P. O. Box 129, Sterling, Kansas 67579
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-3-73 19____
Application for plugging filed 5-21-73 19____
Application for plugging approved 5-21-73 19____
Plugging commenced 10:30 AM, 5-26-73 19____
Plugging completed 12:30 PM, 5-26-73 19____
Reason for abandonment of well or producing formation _____
Dry Hole
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4067' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	281'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
Down 8 5/8" surface casing Howco Plug
with 3 sacks hulls and 25 sacks gel
and 120 sacks Pozmix #1. 2 sacks in
rathole.

RECEIVED
STATE CORPORATION COMMISSION
MAY 30 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sterling Drilling Company
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
Bernard Laudermilk (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) Bernard Laudermilk
Bernard Laudermilk, Vice president
P. O. Box 129, Sterling, Kansas 67579
(Address)

Subscribed and sworn to before me this 29 th day of May, 19 73.

My commission expires _____
STERLING DRILLING COMPANY
STERLING, KANSAS
Charles M. Hall
Charles M. Hall,
Notary Public.
CHARLES M. HALL—NOTARY PUBLIC
My Commission Expires Jan. 6, 1974

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- FLESKE #1
Located: NE NE SW, Section 13-22S-16W, Pawnee County, Kansas

OWNER: Sterling Drilling Company, Anadarko Production Company and
Martin Oil and Gas Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 24, 1973

COMPLETED: May 3, 1973

TOTAL DEPTH: 4067'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 290 Shale and Sand	Ran 6 joints 8 5/8" pipe, 269.40' cemented at 281' K.B. with 225 sacks 60/40 Pozmix, 2% gel, 3% HA-5. Plug down at 4:00 PM, 4-24-73.
290 - 1250 Red Beds and Sand	
1250 - 1860 Shale and Shells	
1860 - 3078 Lime and Shale	
3078 - 3515 Lime	
3515 - 3565 Shale and Lime	
3565 - 3573 Lime (Brown)	
3573 - 3665 Lime (Lansing)	
3665 - 3880 Lime	
3880 - 3947 Lime, Shale, Chert	
3947 - 3975 Sandy Cherty Cong.	
3975 - 4025 Lime and Shale	
4025 - 4031 Lime (Arbuckle)	
4031 - 4047 Lime	
4047 - 4067 Arbuckle	Plugged.