

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Pawnee County, Sec. 13 Twp. 22S Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW

Lease Owner Alpine Drilling Co. & Sterling Drilling Co.

Lease Name Unruh Well No. 1

Office Address 800 Bitting Building, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 27 1975

Application for plugging filed July 27 1975

Application for plugging approved July 27 1975


Plugging commenced July 27 1975

Plugging completed July 27 1975

Reason for abandonment of well or producing formation Non-producing in commercial quantities

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Don Truan

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4060 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	285'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged with 50 sacks cement at 400', 25 sacks at 240',  
plug and 1/2 sack hulls at 40', 10 sacks cement.  
Plug down 1:15 a.m. July 27, 1975.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 29 1975

7-29-75

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Allied Cementing Co., Inc.  
Address Box 31, Russell, Kansas 67665

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Jon T. Williams, Jr. (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jon T. Williams, Jr.  
800 Bitting Building, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of July, 1975

February 23, 1976

Patricia J. Phillips  
Patricia J. Phillips Notary Public.



STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- UNRUH #1  
Located: NW NW NW, Section 13-22S-16W, Pawnee County, Kansas

OWNER: Alpine Drilling Company  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: July 18, 1975  
COMPLETED: July 27, 1975

TOTAL DEPTH: 4060'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Sand and Clay	Ran 7 joints used 8 5/8" casing, 271.79' set at 283' K.B. with 225 sacks Common with 2% gel and 3% cc. Plug down at 2:00 PM, 7-18-75, by Allied.
90 - 285 Shale and Sand Strgs.	
285 - 1003 Shale, Sand and Shale	
1003 - 1025 Anhydrite	
1025 - 1835 Shale, Red Beds, Shells	
1835 - 2057 Shale Shells	
2057 - 3610 Lime and Shale	
3610 - 3890 Lime	
3890 - 3975 Lime and Cong.	
3975 - 4000 Lime and Shale	
4000 - 4032 Cong.	
4032 - 4043 Arbuckle	
4043 - 4060 Lime and Shale	Plugged.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 4 1975

CONSERVATION DIVISION  
Wichita, Kansas

YOUR COPY