


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Reno County. Sec. 30 Twp. 22 Rge. 9 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SW SE SW
Lease Owner Cities Service Oil Company
Lease Name Peace Creek Unit, Tract 1 Well No. 1
Office Address Box 144, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed June 6 19 42
Application for plugging filed August 15 19 58
Application for plugging approved August 18 19 58
Plugging commenced September 3 19 58
Plugging completed September 10 19 58
Reason for abandonment of well or producing formation Depleted formation

If a producing well is abandoned, date of last production January 23, 19 58
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation Viola Depth to top 3676 Bottom 3706 Total Depth of Well 3706 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	273'	None
				7"	3689'	1517'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3706-3675', river sand.
3675-3645', 5 sacks cement.
3645- 210', heavy mud.
210- 175', rock bridge and 25 sacks cement.
175- 35', heavy mud.
35' to base of cellar, rock bridge and 15 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 13 1958
CONSERVATION DIVISION
Wichita, Kansas
9-13-58

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C. E. Shull Casing Pulling Co.
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
V. M. Conover (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. M. Conover
Box 144, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of September, 19 58
W. G. Smith
Notary Public.

My commission expires March 12, 1959.

PLUGGING
FILE SEC 30 T. 22 R. 9W
BOOK PAGE 123 LINE 19

15-155-03209-0000

Peace Creek Unit

WELL - J. C. SMISOR #1 (TRACT #1)

Total Depth	3,706 feet
Spudded	5-26-42
Complete	6-21-42
Surface Casing	10 3/4" @ 276' w/200 sx
Production Casing	7" @ 3689' w/200 sx
Initial Production	
Top Producing Formation	3,676 feet
Bottom Producing Formation	3,706 feet
Elevation	1,727 feet ground 1,729 feet derrick floor
Remedial Work	None

STATE OF KANSAS

AUG 18 1942

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 30 T. 22 R. 9W
BOOK PAGE 123 LINE 19